

VESSEL'S NAME S.S. "CROSTAFELS" REPORT Bremen No. 197

THICKNESSES OF PLATING ascertained by drilling, and comparison of same with the original thicknesses.

The thicknesses are in hundredths of an inch.

STRAKE.	AMIDSHIP.						FORWARD.						AFT.						REMARKS.
	Original Thickness	Thickness by drilling.		Diminution if any.		Original Thickness.	Thickness by drilling.		Diminution if any.		Original Thickness.	Thickness by drilling.		Diminution if any.					
		Port.	Std.	Port.	Std.		Port.	Std.	Port.	Std.		Port.	Std.	Port.	Std.				
BRIDGE SHEER STRAKE	N	70.	67.	63.	3	7.	42.	47.	47.	-		40.	47.	47.	-		Additional		
Strake below	M	66.	55.	55.	11.	11.	42.	59.	59.	-		40.	59.	59.	-		drillings in		
SHEER STRAKE	L	66.	59.	59.	7.	7.	46.	55.	51.	-		46.	51.	51.	-		2nd strake below		
1st Strake below	K	66.	51.	55.	15.	11.	46.	49.	49.	-		46.	47.	47.	-		in way of bridge		
2nd "	J	66.	51.	43.	15.	23.	46.	47.	47.	-		46.	47.	47.	-		at: -		
3rd "	H	66.	51.	53.	15.	13.	46.	51.	51.	-		46.	51.	51.	-		Frame No. p s		
4th "	G	66.	59.	63.	7.	3.	46.	51.	51.	-		46.	51.	51.	-		64 59 55		
5th "	F	66.	63.	63.	3.	3.	46.	67.	67.	-		46.	67.	67.	-		73 51 55		
6th "	E (Bridge)	66.	71.	71.	-	-	48.	-	-	-		48.	-	-	-		98 43 59		
7th "	D	66.	63.	61.	3.	5.	48.	51.	51.	-		48.	51.	51.	-		104 51 47		
8th "	C	68.	63.	57.	5.	11.	48.	51.	51.	-		48.	51.	51.	-				
9th "	B	68.	63.	63.	5.	5.	48.	59.	55.	-		48.	59.	59.	-		*Plate renewed		
10th "	A	68.	63.	63.	5.	5.	48.	63.	63.	-		48.	63.	63.	-		part doubled.		
xxx Keel		106.	83.		23.		74.	71.	-	3.	-	74.	67.	-	7.	-			
xxx																			

Drillings at ends to be made in the vicinity of the peak bulkheads.

002633-002658-0069

Lloyds Register  
Foundation

W. H. Allen  
Surveyor.