

15/11 'alfred blegg'

Carrying petroleum in bulk

Built by Messrs. Burmeister & Wain.

The plan of general Pumping arrangement has been examined & found in order.

The plan of Oil Fuel Burning arrangement has also been examined & it is noted that two complete oil fuel burning units have not been fitted as required by the Rules, the present installation comprising two pumps, one heater, two suction filters and a discharge filter fitted at each burner.

It is submitted that the attention of the Copenhagen Surveyors be drawn to the above remarks & they should be informed that since most of the auxiliaries required for essential services at sea are steam driven, the Rule requirements regarding the provision of two complete oil burning units should be complied with, and the owners should be asked to arrange for the provision of an additional oil fuel heater & a duplex discharge strainer.

Return

plan.

Retain

copy.

2500.11.39. T.

002667-002673-0051

Lloyd's Register  
4803  
41146