

LONDON
COPY.

16 SEP 1955

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "CARROWDORE" Official No. 132047


Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in _____

ALTERATION TO HATCHWAYS NOS 1 & 2.

Existing arrangement of single strong beam with wood fore and afters dispensed with and new hatch closing wrgt. fitted as follows.

		Nº1	Nº2	
Description of Hatchway	Upper Deck	R.Q. Deck	
Dimensions of Hatchway	29'-6" x 16'-3"	31'-2" x 16'-3"	
COAMINGS	Height above Deck	
	Thickness	Sides	...	
		Ends	...	
	Stiffeners	
	Brackets, Stays	
		NO ALTERATION		
HATCH BEAMS	Number	5	5	
	Spacing	4'-11"	5'-2 1/3"	
	Scantling and Sketch	
	WEB	14 x 34	12 x 30	
	TOP & BOTTOM BARS	3 1/2 x 3 x 42	3 1/2 x 3 x 42	
	Bearing Surface	3"	3"	
FORE AND AFTERS	Number	
	Spacing	
	Unsupported Lengths	
	Scantling* and Sketch	
	Bearing Surface	
HATCH COVERS	Material	W.W.	W.W.	
	Thickness	2 3/8"	2 3/8"	
	How fitted	F & A	F & A	
	Bearing Surface	3 1/2"	3 1/2"	
Spacing of Cleats	...	24"	24"	
Number of Tarpaulins	...	2	2	
*Are wood fore and afters steel shod at all bearing surfaces?				✓
Are battens and wedges efficient and in good condition?				Yes ✓
Are tarpaulins in good condition and in accordance with rule requirements?				Yes ✓
Are lashings provided in accordance with rule requirements?				Yes ✓


A copy of this report was placed on board the ship.



Any ship M

checked.

Arrangements as approved
See Ship Letter 29/7/55



© 2020
Lloyd's Register
Foundation
22 SEP 1955