

CLASS CONTEMPLATED.

(LLOYD'S REGISTER.)

G.R. 130.
Lloyd's Register.

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of British and Foreign Shipping, Signal Letters (if any) G.Y.T.Y.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
164,919.	Admiral Drake.	28/1936 Hull.

No., Date, and Port of Previous Registry (if any). -----				
Whether British or Foreign Built.	Whether a Sailing Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Single Screw.	Selby	1936.	Messrs. Cochrane & Sons Limited, Selby.
Number of Decks	One & Raised Quarter Deck	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post	Feet.	Tenths.
Number of Masts	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel	152	8
Rigged	Ketch	Main breadth to outside of plank	25	6.5
Stern	Cruiser	Depth in hold from tonnage deck to ceiling at midships	13	6.5
Build	Clencher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards		
Galleries	None	Depth from top of beam amidships to top of keel		
Head	Straight Stem	Depth from top of deck at side amidships to bottom of keel		
Framework and description of vessel	Steel Trawler	Round of beam	33	6.7
Number of Bulkheads	Five	Length of engine room, if any		1.5
Number of water ballast tanks, and their capacity in tons	None			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ----- Tons. Ditto per inch immersion at same depth ----- Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. B. H. P. I. H. P. Speed of Ship.
					No. and Diameter of Cylinders in each set.	Length of Stroke.	No. of Cylinders in each set.	
One	Reciprocating Steam Triple Expansion Direct Acting	Engines. British	Engines. 1936	Engines. Charles D. Holmes & Co., Ltd., Hull.	Three			N. H. P. 105
No. of Shafts.	Inverted Cylinder				13 1/2"			I. H. P. 650
	Description. Cylindrical Multitubular Boilers	Boilers. British	Boilers. 1936	Boilers. Charles D. Holmes & Co., Ltd., Hull.	23"	26"	----	11 1/2 knots.
	Number One				37"			
	Iron or Steel Steel							
	Loaded Pressure 200 lbs							

PARTICULARS OF TONNAGE.

GROSS TONNAGE.		No. of Tons.	DEDUCTIONS ALLOWED.		No. of Tons.
Under Tonnage Deck		362.82	On account of space required for propelling power		195.37
Space or spaces between Decks			On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew		
Turret or Trunk			These spaces are the following, viz.:-		
Forecastle House in		1.82	Below Deck fwd & aft.		42.95
Bridge space			(Number of Seamen or Apprentices for whom accommodation is certified... 17.....)		
Peep or Break		20.41	Under Forecastle & on R.Q.D.		
Side Houses		13.84	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—		
Deck Houses		3.02			
Chart House					
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894		16.49			
Excess of Hatchways					
Gross Tonnage		418.40	Cubic Metres	Master's Accommodation	5.07)
Deductions, as per Contra		256.75		Chart Space	3.02)
Register Tonnage		161.65		Wireless Telegraphy Space	1.97) 18.43
				Boatswain's Store	8.37)
				Total	256.75

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 95.15 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 17.53 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Open Forecastle Length 24'.3 - 15.77 Tons.

Name of Master	Certificate of { Service No. Competency No.
No. of Owners	
Name, Residence, and Description of Managing Owner if there are more owners than one.	
C.H. Smith & Co. (Hull) Limited 102, Gillett Street, Kingston-upon-Hull. Sixty-four (64) shares.	Archibald Hudson St. Catherines, Swanland Road, Hessle, E. Yorks. -Manager-

Dated 20th April, 1936



Lloyd's Register Foundation

052674-002681-0019