

REPORT ON ELECTRIC PROPELLING MACHINERY

17 NOV 1948

Received at London Office

Date of writing Report 10-1948 When handed in at Local Office 19 Port of LIVERPOOL

No. in Survey held at BIRKENHEAD Date, First Survey 3/8/48 19 Last Survey 10-10-1948
Reg. Book. No. of Visits

59465 on Single Screw vessel "FORT STEVENS" Tons Gross 10639 Net 6274

Built at MOBILE, ALA. By whom built ALABAMA D.D. S.B. Co. Yard No. - When built 1944

Electrical Machines made at SCHENECTADY By whom made GENERAL ELECTRIC Co. Generator Nos. 5840760 When made 1944
Motor Nos. 5690826

Shaft Horse Power at Full Power 6000/6600 Total Capacity of Generators 4925/5400 kilowatts

Machinery Numeral as per Rule 1058 Owners BRITISH TANKER Co. Ltd. Port belonging to LONDON

Trade for which Vessel is intended CARRYING PETROLEUM IN BULK.

LANS.— Have plans of the Machines, Control Gear, Cables and Circuits been submitted and approved Typical plans of 12 Tanks approved.

TEAM ENGINES.— Type of Engine Steam Turbine No. of Engines one R.P.M. 3600/375 Is a Governor fitted Yes Is the speed variation as per Rule when load is thrown off - Is an Emergency Governor fitted Yes Is it arranged for hand tripping Yes Does it trip the throttle valve Yes If exhaust steam is admitted, is an automatic shut-off fitted - Is provision made for bled steam NO and is a non-return or positive shut-off valve fitted - Lubricating Oil.— State means provided for emergency supply Gravity Tank Is the emergency reserve sufficient to maintain lubrication as per Rule Yes Mechanical Balance.— Are the Engines and Generators balanced so as not to cause appreciable vibration Yes

MIL ENGINES.— Type of Engines - R.P.M. - Is a Governor fitted - Is the speed variation as per Rule when load is thrown off - Is an Emergency Governor fitted - Does it operate as per Rule -

GENERATORS.— Direct or Alternating Current A.C. No. of Generators one If A.C. state frequency at full load 60/62 cycles. Kw. per Generator 4295/5400 Volts per Generator 2300/2370 Amps. per Generator 1237/1315 Have certificates of works tests been supplied No and the results found as per Rule - Ventilation.— State how arranged (open or closed system) 6 local systems

Are ventilating arrangements satisfactory Yes Heating when Idle.— What provision is made Electric heaters located within inner shields of generator. Facilities for Inspection and Repair.— Are these as per Rule Yes

Are wear-down gauges supplied No Bilges.— Are the arrangements to prevent accumulation of bilge-water under the machines satisfactory Yes

MOTORS.— S.H.P. per Motor at full power 6000/6600 No. of Motors one Single or double unit single Volts per Motor 2300/2370 Amps. per Motor 1160 Have certificates of works tests been supplied No and the results found as per Rule - A.C. Motors.— Is provision made for machining the slip rings No Do the Motors remain in synchronism under all normal conditions of running Yes D.C. Motors.— If the system permits overspeeding at light loads are overspeed protection devices fitted -

EXCITATION.— Is power for excitation taken from the ship's Auxiliary Generators Yes If so, state voltage 110 and excitation amperes at full power 175 kilowatts for excitation 75 State excitation arrangements for Propulsion Generators Excitation for both propulsion generators and motor provided by a 75Kw exciter driven by combined turbo sets consisting of 400Kw alternator, 75Kw exciter and Propelling Motors and 55Kw D.C. Generator. Is an alternative means of excitation provided Yes - Two aux sets provided. Have certificates of works tests been supplied No and found as per Rule -

CONTROL.— Position of Main Control Panel In main engine room at starting platform.

Does it comply with the requirements regarding position Yes, grouping of controls Yes, instruments Yes, insulating materials (state type used) Appears to be "Sindensyn" type of synthetic insulating material, spacing and shielding of live parts Yes, accessibility Yes, position of fuses Yes, locking of screws and nuts Yes, labelling Yes, fuses for voltmeters, pilot lamps, etc. Yes, provision for manual operation of contractors, etc. (state method employed) Contractors manually operated by lever, interlocked against incorrect operation.

earthing of instrument cases above 250 volts to earth Yes, provision of renewable tips on switches subject to arcing Yes, capability of withstanding shock and inclination Yes, operation with high and low voltage Yes, rust proofing of parts. Overload and Short Circuit Protection.— State means provided Phase balance relay for protection against phase faults resulting from short circuit between phases or open circuit in one phase. Fault trips excitation breaker.


At what load is it set to operate 25% out of balance Has it been tripped by hand when running at full power and found satisfactory Yes Are fuses of an approved type All fuses are standard American Cartridge type.

Earth Detection.— Is the main circuit provided with means for detecting earths Yes Are aural and visual alarms fitted Visual Is main power interrupted by an earth fault Yes If a limiting resistance is in the earth detecting circuit what is the ohmic value 670 ohms What earth leakage current is necessary to operate the device Max 0.5 amp If a switch is used to disconnect the aural signal does it automatically give visual indication - Are the excitation circuits provided with means for earth detection Yes Mechanical Protection.— Are circuits above 250 volts to earth protected as per Rule Yes

Bridge or Deck Control.— Is bridge control provided No If so, from how many stations - can it be operated freely without producing currents or loads in excess of the working capacity of the plant - and without reference to electrical instruments - Is an emergency control provided in the engine room - and can the transfer to this control be made quickly in the engine room - Can the emergency control be rendered mechanically independent of the deck control - Instruments and Gauges.— State Instruments provided for each Generator Temp. Indicator, Fuses and full volt and ammeter, Speed indicator, Generator Volt-ammeter, Phase balance relay, earth relay and for each Motor Temp Indicator, Full-line Volt-ammeter, H.P. Meter, Revolution Indicator an Insulation Tester provided Yes

Discharge Protection.— Are all shunt field circuits protected as per Rule Yes D.C. Systems.— If the Generators are connected in series state means provided to prevent reversal of direction of rotation of the Prime Movers -

Are the Propulsion Generators also used alternatively for other purposes Yes - for driving cargo stopping pumps through transformers. If so, is provision made for overload protection, voltage adjustment, etc. Yes



Reversing Switches.—If any are provided are they interlocked as per Rule Yes Resistances.—Are resistances for synchronous motor fields insulated as per Rule Yes Temperature Alarm.—Are machines with enclosed ventilating system, etc., fitted with temperature alarm Indicators only.

CONDUCTORS & CABLES.—Are all essential Conductors stranded as per Rule Yes Are the ends of Paper and Varnished Cambric Insulated Cables sealed Yes Are all Cables carrying A.C. constructed and installed as per Rule Yes Have all Cables been tested at the makers' works. —

SECONDARY BATTERIES.—Are Batteries used for starting Main Propulsion Engines No If so, have full particulars of rating been submitted and approved — Have they been tested under working conditions and do they give the required number of starts — Are they installed as per Rule — Are the charging arrangements satisfactory —

SPARE GEAR.—If engaged on open sea service has a list of spare gear been submitted and approved No Is a list of the articles supplied attached to this report No Are they stored as per Rule Yes

ELECTRIC PROPULSION EQUIPMENT CONDUCTORS.

DESCRIPTION	CONDUCTORS.		TOTAL MAXIMUM CURRENT—AMPERES.*			MAXIMUM VOLTAGE TO EARTH.	INSULATED WITH.	DI-ELECTRIC THICKNESS.	HOW PROTECTED.
	No. per Pole.	Nominal Area per Pole. C. Sq. In.	In Circuit.		Rule Am. Ratio				
			When Running.	When Manoeuvring.					
MAIN GENERATORS	3	3000000	1315		1708	2300	V. C.	-	L.C.A.
GENERATOR FIELDS	1	500000	165	375 R.A.M.	444	110	"	-	"
MAIN MOTORS	3	3000000	1160		1708	2300	"	-	"
MOTOR FIELDS	1	500000	420		444	110	"	-	"
CONTROL CIRCUITS									
OTHER CIRCUITS:—									

*For field circuits the "Hot" and "Cold" value should be given.

The foregoing is a correct description,

Electrical Engineers.

Date

COMPASSES.—Are Single-Conductor circuits carrying direct current arranged with lead and return Conductors fitted as close to one another as possible

Have tests been made during adjustment of the Compasses to determine the effect of switching the main circuits on and off

Builders' Signature.

Date

Is this machinery duplicate of a previous case Generally similar to other T2 Tanks. If so, state name of vessel El. Netto, Tubulus, Soudreylos etc de

General Remarks (State quality of workmanship, opinions as to class, &c.) The Electrical Propulsion Equipment of this vessel appears to be installed in accordance with American practice and the typical plans of T2 Tanks. The details of this report were obtained from these plans and instruction book & personal observation.

The machinery was examined and tested under working conditions & found satisfactory. The equipment appears in good and efficient condition & that it strictly is in accordance with the Society's Rules, it is, in my opinion, eligible for classification.

Note sent 6/12/48

See Dept 9 attached.

The amount of Entry Fee ... £	:	:	When applied for,	10
Travelling Expenses (if any) £	:	:	When received,	19

L. Staffus

Surveyor to Lloyd's Register of Shipping.

Date LIVERPOOL

Committee's Minute



The Surveyors are requested not to write on or below the space for Committee's Minute.