

S/S "LAILA"

ANTWERP. FEBRUARY. 1948.

PARTICULARS OF PROTECTION TO OPENINGS, ETC.

HATCHWAYS ON FREEBOARD AND SUPERSTRUCTURE DECK.									
Description of Hatchway		N° 1	N° 2	N° 3	N° 4				
Dimensions of Hatchway		24' x 18'	26' x 18'	24' x 18'	24' x 18'				
COAMINGS	Height above Deck	AT Sides		2' 8"		11' x 3 1/2' x 1/2'			
	Thickness	Sides		4 1/4"					
	Stiffeners	Ends		4 1/4"					
	Brackets, Stays			8 x 3 x 1/2 BA. 2" DIA SOLID	2 PER HATCH				
HATCH BEAMS	Number	5	5	5	5				
	Spacing	4'-0"	4'-4"	4'-0"	4'-0"				
	Scantling and Sketch			8" x .75" FLANGE					
	Bearing Surface			.36" WEB 8" x .75" FLANGE. 4"					
FORE AND AFTERS	Number								
	Spacing								
	Unsupported Lengths								
	Scantling* and Sketch								
HATCH COVERS	Material			WOOD					
	Thickness			2 1/2"					
	How fitted			F & A					
	Bearing Surface			3"					
Spacing of Cleats				2 1/4"					
Number of Tarpaulins				3					
<p>*Are wood fore and afters steel shod at all bearing surfaces? <input checked="" type="checkbox"/> YES.</p> <p>Are battens and wedges efficient and in good condition? YES.</p> <p>Are tarpaulins in good condition and in accordance with rule requirements? YES.</p> <p>Are lashings provided in accordance with rule requirements? YES. 3 LOCKING BARS FITTED AT EACH HATCH.</p>									

Particulars of any special features:—

Hayman



© 2021

Lloyd's Register Foundation