

G.R. 136.

(LLOYD'S REGISTER.)

VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.

Signal Letters (if any) G.Z.F.P.

Official Number.	Name of Ship.	No., Date, and Port of Registry.
<u>165,349.</u>	<u>Tornus</u>	<u>246 in 1936 London.</u>

No., Date, and Port of Previous Registry (if any). Purchased from Sarawak as Tornus.

Whether British or Foreign Built.	Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
Foreign	Motor Ship Single Screw.	Vege sack	1936	Bremer Vulkan Vege sack.
Number of Decks ..	One	Length from fore part of stem, under the bowsprit, to the aft side of the head of the stern post ..	Feet.	Tenths.
Number of Masts ..	Two	Length at quarter of depth from top of weather deck at side amidships to bottom of keel ..	465	----
Rigged ..	Not	Main breadth to outside of plank ..	59	4
Stern ..	Cruiser	Depth in hold from tonnage deck to ceiling at midships ..	33	8.5
Build ..	Clencher	Depth in hold from upper deck to ceiling at midships, in the case of three decks and upwards ..		
Galleries ..	-----	Depth from top of beam amidships to top of keel ..		
Head ..	Straight	Depth from top of deck at side amidships to bottom of keel ..		
Framework and description of vessel ..	Steel Oil Tanker	Round of beam ..	1	2
Number of Bulkheads ..	Eighteen	length of engine room, if any ..	73	5
Number of water ballast tanks, and their capacity in tons	Four = 5257 tons.			

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel 15087 Tons. Ditto per inch immersion at same depth 55.6 Tons.

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. E. H. P. I. H. P. Speed of Ship.
One	Internal Combustion Diesel.	Engines. Foreign	Engines. 1936	Engines. Maschinenfabrik Augsburg-Nurnberg Augsburg Deutsche Werft Hamburg.	Eight	1400 m/m	-----	502 estimated 3500 " 4200 " 12 Knots "
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.					
One	Scotch	Foreign	1936					
	Number One							
	Iron or Steel S.M. Steel							
	Loaded Pressure 180 lbs.							


PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ..	7223.57	On account of space required for propelling power	2577.15
Space or spaces between Decks ..		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	
Fore-cabin or Trunk ..	.16	These spaces are the following, viz.:—	
Forecastle ..	113.16	Poop, Forecastle and Round Houses	437.91
Bridge space ..		(Number of Seamen or Apprentices for whom accommodation is certified.....59.....).	
Poop or Break ..	213.30	Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Side Houses ..	69.36		
Deck Houses Round ..	214.97		
Chart House ..	8.51		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ..	210.55		
Excess of Hatchways ..	-----		
Gross Tonnage ..	8053.58	Cubic Metres.	
Deductions, as per Contra ..	3297.22	Masters Accommodation 22.88	} 282.16
Register Tonnage ..	4756.36	Chart Space 8.51	
		Wireless Telegraphy Space 5.90	
		Boatswains Stores 75.00	
		Ballast Pump Space 33.16	
		Water Ballast Space 136.71	} 3297.22

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 843.49 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 242.25 tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage. Bridge Length 47' = 130.37 tons.

Name of Master	Certificate of	Service No.	No. Competency No.
No. of Owners			
Name, Residence, and Description of Managing Owner if there are more owners than one.			
<u>The Anglo Saxon Petroleum Company Limited</u>		Andrew Agnew of	
<u>St. Helens Court, Leadenhall Street, London.</u>		same address—Manager—	
<u>Shares Sixty-four.</u>			
<u>Dated 21st November 1936.</u>			



81438
P.28 ft.
not give
Water Capacity. Tons. 139.3 85.4 272.0
71418
1,2428
2526
1,3
715 81

36
54
56
gle
90.2
2
2
the
tube
m
feet
tion
with
and
ing
ing
ilge
ices
one
me
52