

15 APR 1944

Rpt. C. 11 (Contd.)

Index No.

GLASGOW REPORT No. 68330.

Lloyd's Register of Shipping.

Ship's Name "LOCH DEE"

Official No. 164122

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

COMPANIONWAY: A companionway, strongly built of steel, fitted on shelter deck aft for access to new gunners' quarters in No. 5 shelter 'tween decks, opening 4'1" x 2'0½", sill 18", closed by a strong hinged steel door capable of being operated from both sides.

SIDELIGHTS: Sidelights fitted in shell in way of new gunners' accommodation, 10" dia. of strong construction and fitted with strong hinged deadlights.

VENTILATORS: Additional ventilators now fitted to ventilate gunners' accommodation as follows:-

3, 6" dia. cowl ventilators, coamings 30" x .30"	} wood plugs and canvas covers provided.
1, 8" " " " " " "	

SANITARY DISCHARGES: From W.C.s and washbasins &c. in gunners' accommodation, 3 in number, each fitted with double automatic non-return valves in accessible positions.

Geo Cockburn

Glasgow. 12th April, 1944.

A copy of the above has been attached to the copy of the Loadline Report on board the vessel.

Geo Cockburn

Glasgow. 12th April, 1944

Noted
15 APR 1944
J.P.S.

© 2020

Lloyd's Register
Foundation

002711 - 002716 - 0227