

Lloyd's Register of Shipping.

Ship's Name *"CITY OF BARCELONA"*Official No. *161151*

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in _____

ALTERATION I:- OPENING OF SHELTER 'TWEEN DECKS. The opening of the shelter 'tween decks has now been completed by fitting weighted cocks at the bottom ends of scupper pipes draining the shelter 'tween decks to the engine room bilges.

ALTERATION II:- REMOVAL OF GUNNERS ACCOMMODATION. The removal of the Gunners Accommodation situated in the shelter 'tween deck port side aft has now been completed by removing two 9" dia. and two 6" dia. cowl ventilators on the shelter deck port side aft and closing the openings with welded closing plates. By removing eight 10" dia. side scuttles in sheerstrake port side aft and closing the openings with welded closing plates. And by removing one 2" dia. lavatory discharge from shell port side aft and closing the opening with a welded closing plate.

Alex. M. Jenkins
Surveyor to Lloyd's Register of Shipping
LONDON. 18TH JULY 1946.

W. J. J. J.
23 JUL 1946