

17 MAY 1952

40519

Rpt. C. 11 (Contd.)

Index No.

## Lloyd's Register of Shipping.

Ship's Name

Clan Campbell

Official No.

168761

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines

in

This vessel converted from a closed Shelter Deck to an open Shelter Deck.

Foreboard Alterations.

A Luggage Hatch fitted in the Shelter Deck, closed by efficient temporary covers and fitted with a coaming 9" high above Shelter Deck.

An overboard scupper 5" diam fitted p.s. in the Luggage Well with a screw down automatic non-return valve controlled from the Shelter Deck with open and shut indicator.

All Hatchways on the second deck fitted with coamings, covers, supports, bearing surfaces, trussings, cleats and battening arrangements in accordance with the Rules.

All the Scuppers from the second deck are fitted with screw-down Valves operated from the Shelter Deck, with indicators showing open and shut position, and in way of the Machinery Space, the Scuppers are fitted with self-closing cocks at the lower ends in an accessible position.

Jas L. Struthers

Glasgow.

29<sup>th</sup> March 52.

© 2020

Lloyd's Register  
Foundation