

COPY. *for London*

Lloyd's Register of Shipping.

Port of GENOA

24th June 1927 . -



This is to Certify that

Alexander LAWRENCE

the undersigned Surveyor to this Society did at the request of Messrs Ing. Eugenio Massa examine at their works at Genoa on 25th May and subsequently two vertical refrigerating machines, of Messrs J. & E. Hall's CO₂ Type N° 10A, stated to have been constructed at Messrs Hall's works at Dastford, England . -

Each machine is complete with a gas condenser built into the frame, and there is for each group a gas evaporator in a containing tank, the brine return tank being common to the two evaporators . -

The whole of the working parts were opened out, examined and found, together with the coils, tanks and fittings, in apparently new condition . -

Each machine consists of a single gas compressor 4" diameter worked by a steam engine having a single cylinder 1 1/2" diameter x 9" stroke . - A water circulating pump 7" diameter x 6" stroke worked from the crank shaft is attached to each machine

It is stated that this refrigerating machinery is to be fitted on the T.S.S. "CONTE GRANDE", Stabilimento Tecnico Triestino's Hull N° 764, now under construction at Trieste . -

...///...

This Certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that :--

"While the Committee use their best endeavours to ensure that the functions of the Society are properly executed, it is to be understood that neither the Committee nor the Society are under any circumstances whatever to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any entry in the Register Book or other publication of the Society, or for any error of judgment, default, or negligence of the Surveyors, or other Officers or Agents of the Society."

ONTE GRANDE"

(2)

Ref. Machy. - Genoa Rpt. dated 24th June 1927.

In my opinion the machinery is such as would entitle the vessel to have a record of Lloyd's Refrigerating Machinery Certificate, provided the installation on board be constructed in accordance with the requirements of the Rules of Lloyd's Register . -

For identification, each compressor block has been marked on its face thus: - LL

Alex Lawrence

Surveyor to Lloyd's Register . -

Fee Lit. 450.00;

Exps. " 50.00



© 2021

Lloyd's Register
Foundation

0201 2/2