

Principal Dimensions of Steel Twin Screw Steamer of similar type to "CONTE BIANCAMANO".

Builder:- Stabilimento Tecnico Triestino, Trieste.

Owner:- Lloyd Sabaud.

		Feet	Metros.
L x B x P		625.0	190.50
Breadth Mid.		78.0	
Depth Mid. to Shelter Dk.		39.6	12.02
" " " Upper Dk.		31.9	9.70
Camber on all deck beams		3"	
Lower to Main Dk amidships and forward (increased in way of tunnel flat aft as per profile)		8'-0"	
Main to Upper Dk		7'-9"	
Upper to Shelter Dk		7'-9"	
Shelter to Bridge Dk		8'-6"	
Bridge to Promenade Dk		8'-6"	
Promenade to Upper Promenade Dk		10'-3"	
Upper Promenade to Boat Dk		8'-0"	
Deckhouses		7'-6"	
Forecastle & 3rd Class entrance house		7'-6"	
Sheer forward P		11'-6" about	
Sheer aft P		5'-6" "	
Load Draft as per "CONTE BIANCAMANO"		25'-0" B.K.	



© 2021

Lloyd's Register Foundation

002830-002837-0202 W1

-2-

Breadth moulded is 2'-0" more than in the "CONTE BIANCAMANO"
but breadth at Boat Deck and width of deck openings remains
the same.

Completion	1st January 1928
Launch approx.	May 1927
Keel to be laid	September 1926

Particulars supplied by Ing. Cossuta 1.3.26.



© 2021

Lloyd's Register
Foundation

0202-10²/₂