

5 JUN 1957

NEWCASTLE-ON-TYNE, No. F.3792

Index No.

34372
(For London Office use)

/R.

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "JAMAICA PRODUCER" Official No.

Port of Registry Kingston, Jamaica

This ship has been under survey at North Shields

on 11th December, 1956 and the following alterations to the conditions of
assignment of loadlines have now been effected/~~found~~

UPPER DECK BULWARKS:-

The bulwark plating port and starboard has been extended from the bridge
house front forward, to frame 122/3, complete with bulwark rail, stays
and stiffeners.

A freeing port 5'-9" x 9" has been fitted above the sheer strake. P+S

The upper deck house aft and house over, have now been renewed with minor
modifications to suit accommodation.

Upper deck house of steel strongly constructed, with 2 hinged steel watertight
doors in the housefront.

1 hinged steel watertight door at the aft end port and starboard, forming
access to steering gear compartment.

1 strong wood door port and starboard.

House on boat deck of steel, strongly constructed with 1 strong wood door
port and starboard.

All deckhouse doors have 24" coamings and are able to be manipulated from
both sides.


Ventilation of these houses are by the thermo tank system.

The scuppers and sanitary discharges overboard are as fitted originally.

Newcastle-on-Tyne

16th May, 1957.


G. G. YOUNG.



Noted.

12.6.57

A copy of this Report has been placed on board.



© 2020

Lloyd's Register
Foundation

002838-002845-0192