

CARDIFF

3179/3
19 APR 1953

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name "DIMITRIOS A. KYDONIEFS".

Official No. 261

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in _____

CARDIFF.

Existing openings in machinery casing (steel sliding doors) on port and starboard sides within superstructure giving access to stokehold have now been permanently closed by steel welded plates.

2 new openings have been made (1 port and 1 starboard) giving access to engine room, fitted with hinged steel doors operable from either side, 18" sill 24" x 5'1" opening.

2 side bunker hatch coamings on main deck (1 port and 1 starboard) have been removed and openings permanently closed with steel welded plates.

Additional air pipes have been fitted as follows:-

Goose necks fitted to existing air pipes at fore end No.2 tank (port and starboard) 18" above deck, fitted with wire gauze.

2 - 4" air pipes with goose necks, 18" above deck fitted with wire gauze at after end No.2 tank.

No.2a. tank fitted at fore end 4" air pipes (1 port, 1 starboard) with goose necks 18" above deck, fitted with wire gauze. & canvas covers

2 - 4" air pipes (1 port 1 starboard) fitted to settling tanks with goose necks 18" above deck, fitted with wire gauze. & canvas covers

2 - 4" air pipes fitted to No.4 tank (1 port 1 starboard) with goose necks 18" above deck, fitted with wire gauze. + canvas covers to each

[Signature]
SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

11th. March 1953.

The original of the above has been placed on board the vessel.

lie
117 APR 1953