

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

Ship's Name *S.S. "CITY OF LYONS."*

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Alterations and additions effected at *Birkenhead - Nov. 1952.*

Existing crews' accommodation in Poop space extended with access from companionway on P. side - Companionway constructed of steel adequately stiffened having opening 4'-9" x 2'-1" closed by strong wood door operated both sides. Height of sill at opening 8" above deck. A total of 10 additional 9" dia. side scuttles fitted - all with hinged deadlights of approved type.

2 - 2½" dia scuppers fitted discharging overboard below main deck and fitted with storm valves.

new accommodation fitted at after end of Bridge superstructure space - S. side - with access from inside existing house on Bridge deck. Opening 5'-0" x 2'-1" - Sill 8" above deck - and closed by strong wood door operated both sides.

A total of 7 - 12" dia. side scuttles fitted - all with hinged deadlights of approved pattern

3 - 2½" scuppers (2 P. + 1 S.) from existing amidship accommodation on Bridge deck. discharging overboard below main deck and fitted with storm valves.

2 - 2" scuppers from new accommodation in Bridge space discharging overboard below main deck - fitted with storm valves.

1 - 4" and 1 - 2½" scuppers from new accommodation (Hospital) in Bridge space discharging overboard below main deck fitted with gland storm valves.

*H. Marfuchinski
Lloyd's Register
Liverpool 52.
5-11-52*

Copy of above placed on board ship.

noted.

J.B.

see memo (5-12-52)

74 DEC 1952