

## (LLOYDS REGISTER.)

G. R. 130  
Lloyds Register

## VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyds Register of British and Foreign Shipping.

Signal Letters (if any) T.Q.C.H.

Official Number.	Name of Ship.	No., Date, and Port of Registry.		
150170.	Eurimbla.	32 in 1921 Sydney. New South Wales.		
No., Date, and Port of Previous Registry (if any). <b>First Registry</b>				
Whether British or Foreign Built.	Whether a Sailing or Steam Ship; and if a Steam Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.
British	Steam Single Screw	Port Adelaide South Australia	1920/21.	Poole & Steel Limited Port Adelaide South Australia.
Number of Decks	... One & Shade Deck	Length from fore part of stem, under the bowsprit, to the	Feet.	Tenths
Number of Masts	... Two	aft side of the head of the stern post	331	-
Rigged	... Schooner	Length at quarter of depth from top of weather deck at		
Stern	... Elliptical	side amidships to bottom of keel	330	3
Build	... In & Out	Main breadth to outside of plank	47	9
Galleries	... ----	Depth in hold from tonnage deck to ceiling at midships	23	5.5
Head	... ----	Depth in hold from upper deck to ceiling at midships, in the		
Framework and description of vessel	Steel Islerwood Type.	case of three decks and upwards	--	--
Number of Bulkheads	Five	Depth from top of beam amidships to top of keel	27	1
Number of water ballast tanks		Depth from top of deck at side amidships to bottom of keel	26	2
and their capacity in tons	Eight-1207 Tons.	Round of beam	1	-
		Length of engine room, if any	44	5

## PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel ... **6890** Tons. Ditto per inch immersion at same depth ... **32** Tons.

## PARTICULARS OF PROPELLING ENGINES, &amp;c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign made.	When made.	Name and address of makers.	Reciprocating Engines. No. and Diameter of Cylinders in each set.	Length of Stroke.	Rotary Engines. No. of Cylinders in each set.	N. H. P. I. H. P. Speed of Ship.
One	Triple Expansion	Engines.	Engines.	Engines.	Three 25 " 41 " 68 "	45 "	---	333 2300
No. of Shafts.	Particulars of Boilers.	Boilers.	Boilers.	Boilers.				
One	Water Tube Steel Loaded Pressure 180 lbs.	British	1921	Poole & Steel Limited Port Adelaide South Australia.				10½ Knots

## PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck ...	3074.51	On account of space required for propelling power	1072.20
Space or spaces between Decks...		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	208.86
Turret or Trunk ...		These spaces are the following, viz.:— Poop	
Forecastle ...	39.04	Deck Houses, Side Houses	
Bridge space Deck House...	24.56		
Poop or Break ...	105.18		
Side Houses <i>Runy has been sent re. tonnage</i>	65.90		
Deck Houses	97.83		
Chart House	3.62		
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894 ...		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows:—	
Excess of Hatchways ...		Cubic Metres	
Gross Tonnage ...	3350.64	Masters Accommodation 11.26	
Deductions, as per Contra ...	1434.75	Chart House 3.62	153.69
Registered Tonnage ...	1915.89	Wireless Installation 2.66	
		Boatswain's Locker 33.51	
		Anchor Gear 12.14	
		Fore & Aft Peak Tanks 90.50	1434.75

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is **522.50** tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is **95.15** tons.

NOTE 2.—The undermentioned spaces above the Upper Deck are not included in the cubical contents forming the ship's register tonnage.

Wheel House	5.05 Tons	Light & Air Space	95.15 Tons
Galley	12.43 "	Refrigerating Engine Space	5.15 "
Steering Gear	4.92 "	Shelter Deck Space L. 274'	-- 734.22 "
Water Closets	17.10 "		

Name of Master

Certificate of { Service No.  
Competency No.

No. of Owners

Name, Residence, and Description of Managing Owner if there are more owners than one.

William Morris Hughes P.C., M.P., of Melbourne in the State of Victoria, Prime Minister of the Commonwealth of Australia.

Sixty Four Shares.

Dated 3rd December 1921.