

30 JUN 1944

Lloyd's Register of Shipping.

Ship's Name TURKISTANOfficial No. 164156DUNDEE RPT. N^o 9430

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

One Companionway on Bridge Deck, starboard side to gunners accommodation. Strongly constructed of steel 3'-6" x 2'-6" x 6'-3" high. Wood door 4'-6" x 1'-11" operates both sides, sill 1'-6" above steel deck.

8-10" dia side scuttles fitted to shell in Bridge tween decks, strongly constructed & fitted with deadlights.

1-12" dia vent. on Bridge deck, coaming 2'-6" x 36" thick. closed by wood plug & canvas cover. 2- 6" x 4" S.N. vents on bridge deck 2'-6" to opening closed by wood plug.

N.C. & sink discharges discharge overboard below freeboard deck & fitted with storm valves at ship's side.

H. M. Queen

Noted.
30 JUN 1944
H.P.P.



© 2020

Lloyd's Register
Foundation

002897-002906-0230