

## REPORT ON ELECTRICAL EQUIPMENT.

(OTHER THAN FOR THE PROPULSION OF THE VESSEL)

14 SEP 1936

Received at London Office

Date of writing Report 2/9 <sup>1936</sup> When handed in at Local Office 10 Port of Copenhagen  
 No. in Survey held at Odense Date, First Survey 24/7 Last Survey 27/8 1936  
 Reg. Book. 79121 on the Single S. S. Tanker "LOOSDRECHT" (Number of Visits 8)  
 Tons { Gross 9313.51  
 Net 5591.95  
 Built at Odense By whom built Odense Haaskitsvaerk Yard No. 58 When built 1936  
 Owners De Nederlandsche Scheepvaartbedrijf Port belonging to Rotterdam  
 Electric Light Installation fitted by Dansk Elektricitetskompani Contract No. ✓ When fitted 1936  
 Is the Vessel fitted for carrying Petroleum in bulk yes.

## System of Distribution

Two conductor insulated system ✓

## Pressure of supply for Lighting

110 ✓

volts, Heating

volts, Power

110 ✓

volts.

## Direct or Alternating Current, Lighting

direct ✓

Power

direct ✓

If alternating current system, state frequency of periods per second

Has the Automatic Governor been tested and found efficient when the whole load is suddenly thrown on or off yes. ✓Generators, do they comply with the requirements regarding temperature rise yes. ✓, are they compounded wound yes. ✓are they over compounded 5 per cent. yes. ✓, if not compound wound state distance between each generator ✓Where more than one generator is fitted are they arranged to run in parallel no ✓, is an adjustable regulating resistance fitted inseries with each shunt field yes. ✓ Have certificates of test results for machines under 100 kw. been submitted andapproved yes. ✓ Have machines over 100 kw. been inspected by the Surveyors during manufacture and testing ✓Are all terminals accessible, clearly marked, and furnished with sockets yes. ✓, are they so spaced or shielded that they cannot be accidentally earthed,short circuited, or touched yes. ✓ Are the lubricating arrangements of the generators as per Rule yes. ✓Position of Generators engine room, p.s.d.; No. 1 on tween deck, No. 2 on the working floor ✓, is the ventilationin way of the generators satisfactory yes. ✓ are they clear of all inflammable material yes. ✓ if situated near unprotectedwoodwork or other combustible material, state distance of same horizontally from or vertically above the generators ✓ and ✓,are the generators protected from mechanical injury and damage from water, steam or oil yes. ✓, are their axes of rotation fore and aft yes. ✓,Earthing, are the bedplates and frames of the generating plant efficiently earthed yes. ✓ are the prime movers and their respective generatorsin metallic contact yes. ✓ Main Switch Boards, where placed one on tween deck, one in engine room, one generator ✓

If the generators and main switchboard are not placed in the same compartment, is each generator provided with

a fuse on each insulated pole as near as possible to the terminals of the generator, additional to that provided on the main switchboard ✓Switchboards, are they placed in accessible positions, free from inflammable gases and acid fumes yes. ✓, are they protected from mechanicalinjury and damage from water, steam or oil yes. ✓, if situated near unprotected woodwork or other combustible material, state distance of samehorizontally from or vertically above the switchboards ✓ and ✓, are they constructed wholly of durable, non-ignitable non-absorbentmaterials of "Sindanyo" ✓, is all insulation of high dielectric strength and of permanently high insulation resistance yes. ✓,is it of an approved type yes. ✓, if semi-insulating material is used, are all conducting parts insulated from the slab with mica or micanite or othernon-hygroscopic insulating material, and the slab similarly insulated from its framework ✓, is the non-hygroscopic insulating material of an approvedtype ✓, and is the frame effectively earthed ✓. Are the fittings as per Rule regarding:— spacing or shielding of live partsyes. ✓, accessibility of all parts yes. ✓, absence of fuses on back of board yes. ✓, temperature rise ofomnibus bars yes. ✓, individual fuses to voltmeter, pilot or earth lamp yes. ✓, are moving parts of switches alive in the"off" position no ✓ are all screws and nuts securing connections effectively locked yes. ✓ are any fuses fitted on the live side ofswitches no ✓ Main Switchgear, description of switchgear for each generator and each outgoing circuit, and arrangement of equalizer switchesDouble pole circuit breakers with a fuse on each pole. ✓Are turbine driven generators fitted with emergency trip switch as per rule ✓

Are cupboards or compartments containing switchboards composed of

fire-resisting material or lined with approved material yes. ✓

Instruments on main switchboard

1 ✓

ammeters

voltmeters ✓ synchronising device for paralleling purposes. For compound machines is the ammeter connected on the opposite pole to equaliser connection

Earth Testing, state what means are provided at the main switchboard for indicating the state of the insulation of the system

earth lamps fitted. ✓

Switches, Circuit Breakers and Fusible Cut-outs,

do these comply with the requirements of the Rules yes. ✓are the fusible cutouts of an approved type yes. ✓

have the reversed





current protection devices been tested under working conditions ✓ **Joint Boxes, Section and Distribution Boards, is the**  
construction, protection, insulation, material, and position of these as per rule *yes.*  
**Cables:** Single, twin, concentric, or multicore *yes.* are the cables insulated and protected as per Tables IV, V, X or XI of the Rules  
If the cables are insulated otherwise than as per Rule, are they of an approved type ✓ **Fall of Pressure,** state maximum between bus bars and  
any point of the installation under maximum load *5 Volts.* **Cable Sockets,** are the ends of all cables having a sectional  
area of 0.04 square inch and above provided with soldering sockets *yes.* **Paper Insulated and Varnished Cambric Insulated Cables.**  
If conductors are paper or varnished cambric insulated, is the dielectric of the exposed ends of the conductor protected from moisture by being suitably sealed with  
insulating compound ✓, or waterproof insulating tape ✓ **Cable Runs,** are the cables fixed as far as possible in accessible positions  
not exposed to drip or accumulation of water or oil, or to high temperature from boilers, steam pipes, uptakes or other hot objects, or to avoidable risk of mechanical  
damage *yes.* Are cables in machinery spaces, galleys, laundries, bathrooms and lavatories lead covered or run in conduit *yes.*  
**Support and Protection of Cables,** state how the cables are supported and protected *armoured cables used, supported by galv. steel clips, when necessary secured by steel plate casing or laid in galv. steel tubes*  
If cables are run in wood casings, are the casings and caps secured by screws ✓, are the cap screws of brass ✓, are the cables run in  
separate grooves ✓. If armoured and lead covered cables are secured by metal clips, are the clips spaced as per Table VIII *yes.*  
**Refrigerated Chambers,** are the cables and fittings in accordance with the special requirements *yes.*  
**Joints in Cables,** state if any, and how made, insulated, and protected *in joints.*  
**Watertight Glands and Deck Tubes,** are all cables passing through decks and watertight bulkheads provided with deck tubes or watertight glands  
*yes.* **Bushes in Beams and Non-watertight Partitions,** where unarmoured cables pass through beams and non-watertight partitions, are the  
holes efficiently bushed *yes.* state the material of which the bushes are made *lead.*  
**Earthing Connections,** state what earthing connections are fitted and their respective sectional areas ✓  
are their connections made as per Rule ✓  
**Alternative Lighting,** are the groups of lights in the propelling machinery space arranged as per Rule *yes.* **Emergency Supply,** state  
position and method of control of the emergency supply and how the generator is driven ✓  
**Navigation Lamps,** are these separately wired *yes.* controlled by separate switch and separate fuses *yes.* are the fuses double pole *yes.*  
are the switches and fuses grouped in a position accessible only to the officers on watch *yes.*  
has each navigation lamp an automatic indicator as per Rule *yes.* **Secondary Batteries,** are they constructed and fitted as per Rule ✓  
**Fittings,** are all fittings on weather decks, in stokeholds and engine rooms and wherever exposed to drip or condensed moisture, watertight *yes.*  
are any fittings placed in spaces in which goods are liable to be stacked in close proximity to them; if so, how are they protected ✓  
are any fittings placed in spaces where inflammable or explosive dust or gases are liable to be present, if so, how are they protected *the lamps in the  
pumping rooms and bridge space are contained in gastight glass bells protected by the railing  
through galv. steel tubes, carried gastight into lamp fittings.  
where are the controlling switches situated in the saloon house amidships.*  
are all fittings suitably ventilated *yes.* are all switches and lampholders constructed wholly of non-ignitable, non-absorbent materials *yes.*  
**Heating and Cooking Appliances,** are they constructed and fitted as per Rule ✓ are air heaters constructed and fitted as per Rule ✓  
**Searchlight Lamps, No. of** *not fitted* whether fixed or portable ✓, are their fittings as per Rule ✓  
**Arc Lamps,** other than searchlight lamps, No. of ✓, are their live parts insulated from the frame or case ✓, are their fittings as per Rule ✓  
**Motors,** are their working parts readily accessible *yes.* are the coils self-contained and readily removable for replacement *yes.*  
are the brushes, brush holders, terminals and lubricating arrangements as per Rule *yes.* are the motors placed in well-ventilated compartments in which  
inflammable gases cannot accumulate and clear of all inflammable material *yes.* are they protected from mechanical injury and damage from  
water, steam or oil *yes.* are their axes of rotation fore and aft *yes.* *except for the propeller* situated near unprotected woodwork or other combustible  
material, are the motors of the totally enclosed, pipe ventilated, forced draught, drip or flame proof type ✓  
if not of this type, state distance of the combustible material horizontally or vertically above the motors ✓ and ✓  
have machines of over 100 BHP been inspected by the Surveyors during manufacture and testing ✓ **Control Gear and Resistances,** are the generator  
field and motor speed regulators, starters and controllers constructed and fitted as per Rule *yes.* **Lightning Conductors,** where lightning conductors  
are required, are these fitted as per Rule *done* **Ships carrying Oil having a Flash Point less than 150° F.** Have the special requirements of  
the Rules been complied with regarding switches, joint boxes, section and distribution boards, protection of cables, method of distribution, lead of cables, lights and  
fittings *yes.* are all fuses of the filled cartridge type *yes.* are they of an approved type *yes.*  
If portable lamps for use in dangerous spaces are supplied, are they of a self-contained, battery-fed type approved by the Home Office ✓  
**Spare Gear,** if the vessel is for open sea service have spares been supplied as per Rule *yes.*

## PARTICULARS OF GENERATING PLANT.

DESCRIPTION OF GENERATOR.	No. of	RATED AT				DRIVEN BY	WHERE DRIVEN BY AN INTERNAL COMBUSTION ENGINE	
		Kilowatts.	Volts.	Ampères.	Revs. per Min.		Fuel Used.	Flash Point of Fuel.
MAIN ... I.	1	16	110	146	600	1-cyl. steam engine	oil	
MAIN ... II.	1	16	115	140	600	2-cyl. oil engine	oil	160° F.
EMERGENCY ...								
ROTARY TRANSFORMER								

## GENERATOR, LIGHTING AND HEATING CONDUCTORS.

DESCRIPTION.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
	No. per Pole.	Total Nominal Area per Pole Sq. ins.	No.	Diameter.	In Circuit.	Rule.			
MAIN GENERATOR ... I.	1	95	19	2.52	146	147	14	rubber	lead covered and steel wire
EQUALISER CONNECTIONS ...	1	95	19	2.52	140	147	20	"	armoured.
AUXILIARY GENERATOR ... II.									
EMERGENCY GENERATOR ...									
ROTARY TRANSFORMER MOTOR ...									
ROTARY TRANSFORMER GENERATOR ...									
ENGINE ROOM ...									
BOILER ROOM ...									
AUXILIARY SWITCHBOARDS ...									
engine casing	1	50	19	1.83	90	98	46	"	
motor room	1	10	7	1.35	16	38	16	"	
navigation	1	10	7	1.35	5	38	192	"	
ACCOMMODATION ...									
deck house	1	16	7	1.70	40	48.7	168	"	other necessary secured by steel plate casing or laid in galv. steel tubes.
apt.	1	10	7	1.35	30	38	64	"	
WIRELESS ...	1	10	7	1.35	18	38	184	"	
SEARCHLIGHT ...	1	15	1	1.38	1	10	118	"	
MASTHEAD LIGHT ...	1	15	1	1.38	1	10	36	"	
SIDE LIGHTS ...	1	15	1	1.38	05	10	14	"	
COMPASS LIGHTS ...	1	15	1	1.38	1	10	208	"	
POOP LIGHTS ...									
CARGO LIGHTS ...									
ARC LAMPS ...									
HEATERS ...									

## MOTOR CONDUCTORS.

DESCRIPTION.	No. of Motors.	CONDUCTORS.		COMPOSITION OF STRAND.		TOTAL MAXIMUM CURRENT.		Approximate Length. (Lead and Return.) Feet.	Insulated with	HOW PROTECTED.
		No. Per Pole.	Total Nominal Area per Pole Sq. ins.	No.	Diameter.	In Circuit.	Rule.			
BALLAST PUMP ...										
MAIN BILGE LINE PUMPS ...										
GENERAL SERVICE PUMP ...										
EMERGENCY BILGE PUMP ...										
SANITARY PUMP ...										
CIRC. SEA WATER PUMPS ...										
CIRC. FRESH WATER PUMPS ...										
AIR COMPRESSOR ...										
FRESH WATER PUMP ...										
ENGINE TURNING GEAR ...	1	1	35	19	1.83	54	77	28	rubber	lead covered and steel wire
ENGINE REVERSING GEAR ...										
LUBRICATING OIL PUMPS ...										
OIL FUEL TRANSFER PUMP ...										
WINDLASS ...										
WINCHES, FORWARD ...										
WINCHES, AFT ...										
STEERING GEAR—										
(a) MOTOR GENERATOR ...										
(b) MAIN MOTOR ...										
WORKSHOP MOTOR ...	1	1	10	7	1.35	28	38	72	"	
VENTILATING FANS in galley ...	1	1	6	7	1.05	15	28	21	"	
lubricat. oil pump in ...	1	1	6	7	1.35	24	38	47	"	
Fire oil pump in ...	1	1	10	7	1.85	24	38	57	"	



All Conductors are of annealed copper conforming to British Standard Specification No. 7 (or International Electro-technical Commission Publication No. 28).

The Insulated Conductors are guaranteed to withstand the immersion and resistance tests specified in the Rules.

The foregoing is a correct description.

*M. J. J.* **C. J. J. J.** **Elektricitetscompagni**  
**Aktieselskab** *Copenhagen*

Electrical Engineers.

Date 7-9-1936.

#### COMPASSES.

Distance between electric generators or motors and standard compass 14'

Distance between electric generators or motors and steering compass 14'

The nearest cables to the compasses are as follows:—

A cable carrying 5 Ampères 7 feet from standard compass 11 feet from steering compass.

A cable carrying 0.5 Ampères 8" feet from standard compass 8" feet from steering compass.


A cable carrying      Ampères      feet from standard compass      feet from steering compass.

Have the compasses been adjusted with and without the electric installation at work at full power Yes.

Eas the effect of switching on and off circuits, motors and other electro-magnetic apparatus within the vicinity of the compasses been noted Yes.

The maximum deviation due to electric currents was found to be 0 degrees on any course in the case of the standard

compass, and 0 degrees on any course in the case of the steering compass.



Builder's Signature.

Date

Is this installation a duplicate of a previous case No If so, state name of vessel ✓

General Remarks (State quality of workmanship, opinions as to class, &c.)

The electric light & power installation as above described has been fitted in accordance with the Society's Rules, the approved plans and the requirements contained in the Surveyor's letter to date 4/5/1936.

The material used is good description throughout and the workmanship of high class. On completion the installation has been tested as per Rules and found satisfactory.

Noted

Yours

15.9.36

Total Capacity of Generators 32 Kilowatts.

The amount of Fee ... 14.515.20 When applied for, 12.9.36

Travelling Expenses (if any) £ : : 19.9.36

When received, 19.9.36

*Chiliff*  
Surveyor to Lloyd's Register of Shipping.

Committee's Minute

Assigned

*See minute on*  
*J.E. Rpt.*



© 2020

Lloyd's Register  
Foundation