

15 OCT 1948

36807

Rpt. C. 11 (Contd.)

Index No. ....

## Lloyd's Register of Shipping.

Ship's Name "FARNINGHAM"

Official No. ....

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in .....

The vessel has now been converted as an open shelter deck ship and the tonnage hatch aft restored and fitted with temporary covers. ✓

The openings in the tonnage well forward bulkhead closed by portable steel plates secured by hook bolts. ✓

The opening in the after bulkhead of tonnage well now permanently plated over. The scantlings of these bulkheads are in accordance with the Rules. ✓

All the scuppers which are led to the hold bilges from the shelter tween decks now permanently closed by welded plates. ✓

The shelter tween deck spaces now drained to the machinery space bilges by two scupper pipes on each side fitted with self-closing cocks at their ends. ✓

Drain holes are cut in the wings of the tween deck bulkheads to permit of the drainage of water to these scuppers. ✓

An overboard scupper 5' dia has been fitted on each side of tonnage well with a screw down automatic non-return valve controlled from the shelter deck having an indicator showing whether the valve is open or shut. ✓

All the hatch ways on the second deck have coamings, covers, beams, bearing surfaces, tarpaulins, cleats and battening arrangements in accordance with the Rules. ✓


The openings in the machinery casings in the shelter tween decks have bells and closing appliances in accordance with the Rules. ✓

The original gunner's accommodation at tween deck spaces aft now removed, and all sanitary discharges, ventilators, side scuttles serving this space dispensed with and openings in shell and decks permanently blanked off with elect. welded plates. ✓

A copy of the above has been placed on board ship

H. Little

Surveyor to Lloyd's Register of Shipping  
5/10/48.



© 2021

Lloyd's Register  
Foundation

003006 - 003012 - 0031