

Lloyd's Register of Shipping.  
SURVEYS FOR FREEBOARD.  
(COMPUTATION FOR STEAMER, SAILING SHIP, TANKER.)

Ship's Name <b>STANMORE.</b> <b>EX. FORT. JUPITER.</b>	Official Number <b>181816</b>	Nationality and Port of Registry <b>BRITISH.</b> <b>LONDON</b>	Gross Tonnage <b>10995.71</b> <b>10708</b> <b>MT 181448</b>	Date of Build	Port of Survey <b>CARDIFF</b>
Moulded Dimensions: Length <b>503.00'</b> Breadth <b>68.00'</b> Depth <b>39.25'</b> To centre of rudder stock				Date of Survey <b>30. 12. 47.</b>	
Moulded displacement at moulded draught = 85 per cent. of moulded depth <b>24300</b> tons				Surveyor's Signature <b>Dennis Sullivan</b>	
Coefficient of fineness for use with Tables <b>.745</b>				Particulars of Classification <b>Class Contemplated</b>	

<b>DEPTH FOR FREEBOARD (D).</b> Moulded depth ... .. <b>39.25</b> Stringer plate ... .. <b>.08</b> Sheathing on exposed deck $T \left( \frac{L-S}{L} \right) =$ Depth for Freeboard (D) = <b>39.33</b>	<b>DEPTH CORRECTION.</b> (a) Where D is greater than Table depth (D-Table depth) R = <b>(39.33-33.53) 3 = + 17.40</b> <b>5.80</b> (b) Where D is less than Table depth (if allowed) (Table depth-D) R = If restricted by superstructures	<b>ROUND OF BEAM CORRECTION.</b> Moulded Breadth (B) <b>68.00</b> Standard Round of Beam = $\frac{B \times 12}{50} =$ <b>16.32</b> Ship's Round of Beam = <b>18"</b> Difference <b>Excess = 1.68</b> Restricted to Correction = $\frac{\text{Diff}^e}{4} \times \left( 1 - \frac{S_1}{L} \right) =$ <b><math>\frac{1.68}{4} \times .017 = .007</math></b>
---	---	---

## DEDUCTION FOR SUPERSTRUCTURES

	Mean Covered Length (S)	Equivalent Enclosed Length (S <sub>1</sub> )	Height	Height Correction	Effective Length (E)
Poop enclosed ...	108.67	108.67	8.0 ✓	✓	108.67
" overhang ...					
R.Q.D. enclosed ...					
" overhang ...					
Bridge enclosed ...	38.67	38.67	8.0 ✓	✓	38.67
" overhang aft ...					
" overhang forward ...					
F'cle enclosed ...	53.0 ✓	53.00	10.0 ✓	✓	53.00
" overhang ...					
Trunk aft ...					
" forward ...					
Tonnage opening aft ...					
" " forward ...					
Total ...	200.34	200.34			200.34

Standard Height of Superstructure 7.50 ✓

" " R.Q.D. ✓

Deduction for complete superstructure 42.00

Percentage covered  $\frac{S}{L} =$

" "  $\frac{S_1}{L} =$  } 39.83

" "  $\frac{E}{L} =$

Percentage from Table, Line A. Tanker. 30.83.

(corrected for absence of forecastle (if required))

Percentage from Table, Line B.

(corrected for absence of forecastle (if required))

Interpolation for bridge less than .2L (if required)

Deduction =  $42.00 \times .3083 = -12.95$

Percentage from Table, Line A. Tanker. 30.83.

(corrected for absence of forecastle (if required))

Percentage from Table, Line B.

(corrected for absence of forecastle (if required))

Interpolation for bridge less than .2L (if required)

Deduction =  $42.00 \times .3083 = -12.95$

## SHEER CORRECTION.

Station	Standard Ordinate	S M	Product	Actual Ordinate	Effective Ordinate	S M	Product
A.P. ...	60.30	1	60.30	24.00	24.00	1	24.00
$\frac{1}{2}$ L from A.P. ...	26.83	4	107.32	4.00	4.00	4	16.00
$\frac{1}{2}$ L „ ...	6.63	2	13.26	—	—	2	—
Amidships ...	—	4	—	—	—	4	—
$\frac{1}{2}$ L from F.P. ...	13.27	2	26.54	—	—	2	—
$\frac{1}{2}$ L „ ...	53.67	4	214.68	6.00	6.00	4	24.00
F.P. ...	120.60	1	120.60	18.00	18.00	1	18.00
Total ...			542.70				82.00

$$\frac{\text{Mean actual sheer aft}}{\text{Mean standard sheer aft}} = \text{Deficient}$$
$$\frac{\text{Mean actual sheer forward}}{\text{Mean standard sheer forward}} = \text{Deficient}$$

$\frac{\text{Length of enclosed superstructure}}{L}$  forward of amidships =  $\frac{1}{2}$  Tanker  
" " aft of " =  $\frac{1}{2}$  Tanker

Correction =  $\frac{\text{Difference between sums of products}}{18} \left( .75 - \frac{S}{2L} \right) = \frac{460.70}{18} (.75 - .1992) = +14.10$   
 If limited on account of midship superstructure.  $\checkmark$  If limited to maximum allowance of  $1\frac{1}{2}$  ins. per 100 ft.  $\checkmark$

<p><b>Deduction for Tropical Freeboard.</b></p> <p><b>Addition for Winter and Winter North Atlantic Freeboard.</b></p> <p>Depth to Freeboard Deck = <u>39.33</u> Ft.</p> <p>Summer freeboard = <u>9.23</u></p> <p>Moulded draught (d) = <u>30.10</u></p> <p>Deduction for Tropical freeboard and addition for Winter freeboard = <math>\frac{d}{4}</math> inches = <u>7.52" = 7½"</u></p> <p>Addition for Winter North Atlantic Freeboard (if required) = <u>7.52 + 5.03 = 12.55" = 12½"</u></p>	<p><b>Deduction for Fresh Water.</b></p> <p>Displacement in salt water at summer load water line <math>\Delta</math> = <u>21890</u></p> <p>Tons per inch immersion at summer load water line T = <u>67.0</u></p> <p>Deduction = <math>\frac{\Delta}{40 T}</math> inches = <u>8.17</u> = <u>8¼"</u></p>	<p><b>TABULAR FREEBOARD</b> corrected for Flush Deck (if required) <span style="float: right;">88.19</span></p> <p>Correction for coefficient <math>\frac{7.145 + .68}{1.36} = \frac{1.425}{1.36}</math> <span style="float: right;">92.40</span></p> <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th></th> <th style="text-align: center;">+</th> <th style="text-align: center;">-</th> </tr> </thead> <tbody> <tr> <td>Depth Correction ... ..</td> <td style="text-align: center;">17.40</td> <td style="text-align: center;">-</td> </tr> <tr> <td>Deduction for superstructures ... ..</td> <td style="text-align: center;">-</td> <td style="text-align: center;">12.95</td> </tr> <tr> <td>Sheer correction ... ..</td> <td style="text-align: center;">14.10</td> <td style="text-align: center;">-</td> </tr> <tr> <td>Round of Beam correction ... ..</td> <td style="text-align: center;">-</td> <td style="text-align: center;">.25</td> </tr> <tr> <td>Correction for Thickness of Deck amidships ... ..</td> <td style="text-align: center;">-</td> <td style="text-align: center;">-</td> </tr> <tr> <td>Other corrections, scantlings, etc. ... ..</td> <td style="text-align: center;">-</td> <td style="text-align: center;">-</td> </tr> <tr> <td></td> <td style="text-align: center;">31.50</td> <td style="text-align: center;">13.20</td> </tr> </tbody> </table> <p style="text-align: right;">+ 18.30</p> <p style="text-align: right;">Summer Freeboard = <u>110.70</u></p>		+	-	Depth Correction ... ..	17.40	-	Deduction for superstructures ... ..	-	12.95	Sheer correction ... ..	14.10	-	Round of Beam correction ... ..	-	.25	Correction for Thickness of Deck amidships ... ..	-	-	Other corrections, scantlings, etc. ... ..	-	-		31.50	13.20
	+	-																								
Depth Correction ... ..	17.40	-																								
Deduction for superstructures ... ..	-	12.95																								
Sheer correction ... ..	14.10	-																								
Round of Beam correction ... ..	-	.25																								
Correction for Thickness of Deck amidships ... ..	-	-																								
Other corrections, scantlings, etc. ... ..	-	-																								
	31.50	13.20																								

**SUMMER FREEBOARD** amidships from Centre of Disc to top of Deck Line, **Wood**; Steel, Deck :—

SUMMER FREEBOARD MEASUREMENTS		TROPICAL FREEBOARD MEASUREMENTS	
Tropical Fresh Water Line above Centre of Disc	15' 3 1/4"	Tropical Fresh Water Freeboard	7' 11"
Fresh Water Line	8' 4 1/4"	Fresh Water	8' 6 3/4"
Tropical Line	7' 2"	Tropical	8' 7 1/4"
Winter Line below	7' 2"	Winter	9' 10 1/4"
Winter North Atlantic Line	12' 3"	Winter North Atlantic	10' 3 1/4"



A new form should be prepared if any alterations that affect the freeboard have been made. If no such alterations have been made, the Surveyor should endorse the form on this side with his signature and the date.

Roofs.

$$\begin{array}{rcl} \text{Roofs at side} & = & 106.00 \\ \frac{2}{3} \times 4 & = & \frac{2.66}{108.66} \text{ equivalent length.} \end{array}$$

Bridge.

$$\begin{array}{rcl} \text{Bridge at side} & = & 36.00 \\ \frac{2}{3} \times 4 & = & \frac{2.66}{38.66} \text{ equivalent length.} \end{array}$$

Trade of ship \_\_\_\_\_

Names of sister ships \_\_\_\_\_

Builder's name and yard number \_\_\_\_\_

Owners \_\_\_\_\_

Fee £ 20 - - - 6/-

1422



© 2021

Lloyd's Register  
Foundation