

## Lloyd's Register of Shipping.

Ship's Name CLAN FORBESOfficial No. 165951

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1938.

ALTERATIONS - CLOSING TONNAGE OPENING IN SHELTER DECK, ETC.JUNE 1941.

TONNAGE OPENING - On shelter deck, now permanently closed by means of 5" x 3" wood plank, bolted, caulked & payed, except for part on port side where an access hatchway has been provided, as follows -

HATCHWAY - dimensions 4'-6" x 4'-6", coamings 30" high x 4 1/2", 2 3/8" W.P. covers, fitted fore & aft, bearing surface 2 1/2", cleats 24" apart, battens & 2 tarpaulins.

LIFELINES - Provision made for rigging lifelines in all parts of the vessel used by the crew in the working thereof.

SIDE SCUTTLES - Deadlights of side scuttles in cargo spaces below shelter deck now secured by special nuts, only operable by special key, in charge of the master of the vessel.

SCUPPERS - Overboard scuppers (16 + 15) from crew space in shelter tween decks, aft, now permanently closed.

Geo. Cockburn

Glasgow. 19<sup>th</sup> June 1941.

NOTE:- The above has been entered on Rpt. C.11 (contd.) form & the form attached to the copy of Rpt. C.11 on board the vessel.

Regarding other conditions of freeboard assignment, as per assignment letter of 23<sup>rd</sup> May 1941, I have to report as follows -

There are no sanitary discharges from spaces below the shelter deck.

The watertight bulkheads, with the exception of the collision bulkhead & that at fore end of crewspace aft, do not extend to the shelter deck. Notation to this effect to be made in the Register Book.

The Shelter Tween decks, between the above-mentioned bulkheads are drained by scupper pipes to the bilges as per original Rpt. C.11.

This vessel is in an efficient condition & the arrangements for closing hatchways & other openings in the shelter deck are satisfactory.

No freeboard survey (AFS or RFS) has been carried out at this time.

Geo. Cockburn

Glasgow. 19/6/41.

Fee (alterations) £ 5-0-0.

Noted

20/6/41



© 2021

Lloyd's Register  
Foundation