

Lloyd's Register of Shipping.

Ship's Name "CLAN FORBES"

Official No. 165951.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1938

ALTERATIONS - CLOSING TONNAGE OPENING IN SHELTER DK. ETC :-

JUNE 1941.

TONNAGE OPENING - in shelter deck, now permanently closed by means of 5" x 3" wood planking, bolted, caulked & payed, except for part on port side where an access hatchway has been provided, as follows -

HATCHWAY - dimensions 4'-6" x 4'-6", coamings 30" high x 4 1/4", 2 3/8" W.P. covers fitted fore & aft, bearing surface 2 1/2", cleats 24" apart, battens & 2 tarpaulins.

LIFELINES - Provision made for rigging lifelines in all parts of the vessel used by the crew in the working thereof.

SIDE SCUTTLES - Deadlights of side scuttles in cargo spaces below shelter deck now secured by special nuts only operable by special key in charge of the master of the vessel.

SCUPPERS - Overboard scuppers (16 or 15) from crew space in shelter tween decks, aft, now permanently closed.

Geo. Cockburn

Glasgow.

11/12/41



© 2021

Lloyd's Register
Foundation