

W.W. "CALPEAN STAR"

32989

Rpt. C. 11 (Contd.)

Index No. FB 2814

# Lloyd's Register of Shipping.

Ship's Name "HIGHLAND CHIEFTAIN"

Official No. 148161.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

New Hatchway to No. 2 Hold Built on Forecastle Deck Extension.

Description of Hatchway

No. 2

Dimensions of Hatchway

22'-6" x 16'-0"

Coamings ( Ht. above Deck  
( Thickness ( sides  
( ( ends  
( Stiffeners  
( Brackets, stays

24"  
.44"  
.44"  
7" x 3" x .38" BA<sup>S</sup>  
2 @ 1½" solid round stays each side.

Hatch Beams

( Number  
( Spacing  
( Scantling & sketch  
(  
( Bearing surface

5  
4'-1½"  
12" x 6" x 44 lbs. joist  
3"

Fore and afters

None

Hatch Covers

( Material  
( Thickness  
( How Fitted  
( Bearing surface

W.P.  
3"  
F & A  
3"

Spacing of cleats

22" to 24"

Number of tarpaulins

3

Battens, wedges and tarpaulins have been supplied and are in good condition, and in accordance with Rule requirements.

Lashings are provided in accordance with Rule requirements.

*T.R. McIlvenna*

Surveyor to Lloyd's Register of Shipping.

LONDON.

January, 1948.

*Noted  
AR  
20.1.48*

