

Kaiser Co. Inc. Portland. OREGON
T2 - SE- A1 Type Tanker.

Yard No. 125

m.7.43.

GB

nt to Chief Surveyors.....

Received from Chief Surveyors.....

ESSEL'S NAME S. S. "THAUMASTUS" ex. REPORT Gal. No. 4992

"WHITE SANDS"
For the CHIEF SHIP SURVEYOR and CHIEF ENGINEER SURVEYOR.

In cases which have to be submitted to the Classing Committee "the endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case so that the Classing Committee may have all the salient points presented in the endorsement."—(Extract from Sub-Committee's Report, 24/5/92.)

Survey S.S. for Classification and ~~When due~~ Repairs.

This Tanker was built in 1945 and classed with the American Bureau of Shipping.

Notation of 100A1 "Carrying Petroleum in bulk". (Classification Contemplated) and, "Examined 10,47", are assigned.

The GALVESTON Surveyors in a First Entry Report, and Rpt. 8. report 5,48, the vessel examined in drydock and afloat, the scantlings and arrangements verified, the requirements for vessels not built under survey and of a periodical Special Survey complied with.

The deck, bottom and side shell have been cut and strapped at this time.

On account of wear and tear, Electric welding repairs effected to a number of fractured welds ~~at~~ Bulkheads generally.

The equipment of anchors and chain cables on board is equivalent to the Rule requirements and has been tested by the American Bureau of Shipping, except that 30 fathoms of chain cable require to be supplied at the first opportunity.

"Subject to 30 fathoms of chain cable being supplied at the first opportunity."

100A1. "Carrying Petroleum in bulk". "Fitted for oil fuel F.P. above 150° F."

5,48 Gal.
S.S. Gal. 5,48.

Classed 5,48.

1 Dk. 2nd Dk. in way of machinery space. "Elec. Welded".
"Longitudinal Framing"
Cell D.B. uE 82', 26lt, D.T.f. 32'759t, F.P.T. 314t, A.P.T. 60t.
P.K. 14 BH.
P 108', B.36', F.56'.
Machy aft.
O.L. 523.5'
E.S.D.
2 5/16"

Equipment letters for fees g in red.



C.S.S. Records Dept.

to note. Franchises at Bhd 19



Lloyd's Register Foundation

8/10/48

Fitted for oil fuel notation not to be posted pending completion of M.S.

5110-550200-003055-0115