

NOTE:
IN ALL PARTS OF STRUCTURE WHERE 1"-1/8" OR 1 1/4" DIA. RIVETS
ARE SPECIFIED THE HOLES SHALL BE PUNCHED 1/8" LESS IN
DIA. THAN THE RIVET AND REAMED TO SUIT THE RIVET AFTER
THE MATERIAL IS IN PLACE.

SPAR DECK OUTER STRG. $8\frac{1}{2}' \times 5\frac{1}{2}'$ } FOR $\frac{2}{3}$ L. Ø
 SPAR DECK INNER STRG. $72" \times 5\frac{1}{2}"$ } TO 27' AT ENDS
 DOUBLE BUTT STRAPS $1\frac{1}{4}"$ RIV. 5" PITCH.
 INSIDE STRAP $3\frac{1}{2}' \times 32"$ QUAD. RIV.
 OUTSIDE STRAP $24" \times 34"$ TREBLERIV.

L
74" x 51" FOR $\frac{4}{5}$ L. Ø TO 27.5" AT ENDS
DOUBLE BUTTSTRAPS $1\frac{1}{4}$ " RIV. 5" PITCH
INSIDE STRAP $31\frac{1}{2}$ " x 32" QUAD. RIV.
OUTSIDE STRAP 24" x 34" TREBLE RIV.

K

40" FOR $\frac{2}{3}$ L. \otimes TO 25" AT ENDS
DOUBLE BUTTSTRAPS $1\frac{1}{8}$ " RIV. $4\frac{1}{2}$ " PITCH
INSIDE STRAP $28\frac{1}{4}$ " x 25" QUAD. RIV.
OUTSIDE STRAP $21\frac{1}{2}$ " x 28" TREBLE RIV.

J
27" FOR $\frac{3}{4}$ L. Ø TO 19" AT ENDS
QUAD. RIV BUTTLAPS 12" WIDE
 $\frac{7}{8}$ " RIV. $3\frac{1}{2}$ " PITCH.

H
27" FOR $\frac{2}{3}$ L Ø TO 19" AT ENDS
SINGLE BUTT STRAP 22"x32"
QUAD. RIV. $\frac{7}{8}$ " RIV. $3\frac{1}{2}$ " PITCH

G
27" FOR $\frac{2}{3}$ L. Ø TO 19" AT ENDS
QUAD. RIV. BUTTLAPS 12" WIDE
 $\frac{7}{8}$ " RIV. $3\frac{1}{2}$ " PITCH.

E
27" FOR $\frac{2}{3}$ L. TO 19" AT ENDS
QUAD. RIV. BUTTLAPS 12" WIDE
 $\frac{7}{8}$ " RIV. $3\frac{1}{2}$ " PITCH.

STRAKES B.C. $\frac{1}{4}$ " D. 25" FOR $\frac{2}{3}$ L. \emptyset TO 19" AT ENDS
TREBLE RIV BUTTLAPS 9" WIDE $\frac{7}{8}$ " RIV $3\frac{1}{2}$ " PITCH

48"x40" DOUBLE BUTTSTRAPS
INSIDE STRAP 28 $\frac{1}{4}$ " x 25" QUAD. RIV.
OUTSIDE STRAP 21 $\frac{1}{2}$ " x 28" TREBLE RIV.
1 $\frac{1}{8}$ " RIV. 4 $\frac{1}{2}$ " PITCH.

SECTION AT HATCH COAMING "A.A":

DECK PLATING BETWEEN HATCHES 15*

DETAIL OF SIDE KEELSON
LOOKING INBOARD

DETAIL OF CENTER VERTICAL KEELSON.

DETAIL OF KEEL PLATE

DETAIL OF HATCH GIRDER BRACKET.

DETAIL OF INTERMEDIATE WEB

DETAIL OF SIDE TANK
LOOKING OUTBOARD

DIMENSIONS

LENGTH OVERALL -----638'-9"

LENGTH BETWEEN PERPS--615'-0"

BREASTH Moulded 65'-0"

BREADTH MOULDED	36'-0"
DEPTH MOULDED	33'-0"

DEPTH MOULDED 50.5

EQUIPMENT
TWO 9000# STOCKLESS ANCHORS

180 FATHOMS 2³/₈" C.S. STUD LINK CHAIN

300 PATRONS 178 WIRE MOORING CABLE

STR No 797
MIDSHIP SECTION

PRINT No	2060	DRAWING No 3
ISSUED	AUG 1 6 1925	

SCALE: 1/2" = 1'-0"	
AUG.-13-1926	TRACING NO.
AM. S. B. CO.	797-3

MIDSHIP
SECTION



© 2020
Lloyd's Foundation

003656-003064-0258