

Lloyd's Register of Shipping.

Ship's Name "LIBERIAN".

Official No. 164284

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Restoring of the Tonnage Opening as per London letter of the 21st October, 1946, Freeboards assigned to this vessel as an open shelter decker now cut in on ship's side and verified.

- 1. The tonnage opening in the shelter deck now restored and closed by efficient temporary covers. ✓
- 2. Openings in the Tonnage Well bulkheads now closed by 3" Boards in channels as originally. ✓
- 4. The Shelter Tween deck spaces drained to the machinery space bilges by a scupper on each side fitted with self closing cock at the lower ends. ✓
- 6. An overboard scupper 5" diameter fitted on each side of the tonnage well with a screwdown automatic non-return valve controlled from the shelter deck and having an indicator showing when valve is open or shut. ✓
- 7. All hatchways on the second deck have coamings, covers, supports, bearing surfaces, tarpaulins, cleats, and battening arrangements in accordance with the rules. ✓

Renewal Load Line Survey and General Examination carried out at this time. ✓

Fresh Load Line Certificate and copy issued. ✓

A.E. Macdonald

SURVEYOR TO LLOYD'S REGISTER.

LIVERPOOL. 23/10/46.

W. Lead
J.S.D.
14 NOV 1946
J. MacE
15-11-46

[Handwritten mark]

