

Lloyd's Register of Shipping.

Ship's Name LIBERIAN

Official No. 164284

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1936

The following alterations have now been effected consequent upon closing the bonnage opening in the shelter tween decks

Bonnage opening in the shelter deck has been permanently closed by welding a plate on top of bulb angle coaming, Steel companionway, 2 1/2 inch thick wood door and a steel W.T. Ammunition hatch fitted on top of bonnage opening. Sanitary and wash house discharge from gunners accommodation on port side of shelter tween decks space aft fitted with screw down automatic non return valves controlled from the shelter deck.

Four 14" and one 9" side scuttles complete with deadlights fitted in shell plating.

One 6" C.I. goose-neck ventilator fitted to quarters.

Suitable provision has been made for rigging life lines forward and aft by fitting eye plates on deckhouses and life lines supplied.

The shelter tween deck space has been drained to the bilges by fitting a scupper each side at the after end of the shelter tween decks. One scupper each side already fitted in ship and drained to E.R. Bilges.

The W.T. Bulkheads have not been extended to the shelter deck.

Load line survey carried out.

Freeboard marks have been altered and the deck line cut in at the top of steel shelter deck in accordance with assignment note and new certificates issued.

A copy of this memorandum has been forwarded to the owners to be placed on board the ship.

Noted
21/7/41

W. Brown