

6 DEC 1943

Rpt. C. 11 (Contd.)

Index No.
Greenock No. 22502.

Lloyd's Register of Shipping.

Ship's Name " ARDGANTOCK "

Official No. 142271.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in April 1932.

A steel E.W. fabricated combined bathroom and lavatory for the use of the Officers, has been securely installed inside the fiddley casing on the Port side over the main boiler. Approximate dimensions :- 8'-3" by 4'-7 $\frac{1}{2}$ ", height about 7 feet, having hinged steel door 22 $\frac{1}{2}$ " by 4'-7", capable of being manipulated from both sides, with height of sill, 19 $\frac{1}{2}$ ".

Sanitary Discharges, viz: 2 brass non-return valves, 1 W.C. 4" internal dia. and 1, 2" dia. lavatory, have been installed in the Boiler Room, with over-board discharges 25 $\frac{1}{2}$ " below the Raised Quarter Deck, with means of access for overhauling, by ladder in stokehold.

The bath room is arranged with one 18" diameter port scuttle with hinged deadlight, and one 6" dia. mushroom ventilator on the Fiddley top.

Freeman. 4.12.43



© 2020

Lloyd's Register
Foundation