

Messrs.N.V.Kon.Mij."De Schelde"Flushing. (X) Yard No.294.

2,500,6,58 Blk. Sister Ships "ARGO HOLLANDIA", "ARGO ELLAS" & "ARGO CHIOS"

37

Received by Chief Ship Surveyor.....

Received from Chief Ship Surveyor.....

GB

SHIP'S NAME m.s. "ARGO DELOS"

REPORT Rot.

No. 46274

The remarks of the Chief Ship Surveyor are desired on this case for the consideration of the Classing Committee.

("The endorsement to contain a succinct summary of any repairs that have been required and to show the cause or causes of such repairs, and also to bring out clearly any exceptional features in connection with the case, so that the Classing Committee may have all the salient points presented in the endorsement."—Extract from Sub-Committee's Report, 24/5/92.)

L. 468'-1"

B. 65'-7½"

D. 41'-0"

The scantlings and arrangements, as reported, conform with the Society's Revised Rules and Regulations, and are in accordance with or equivalent to those shown on the approved plans.

Additional strengthening for heavy cargoes has been provided and this may be recorded on the Classification Certificate but not in the Register Book as approved by the Committee.

In the deep tanks, however, no heavy cargoes are to be carried.

IT IS THEREFORE SUBMITTED the ship is eligible to be classed:-

*100A1

CSD

~~ESD~~, 2 dks, LF at btm & U dk; EW.
O.L. 516'-9"

Extreme Breadth: 65'-10"

ESD; Rdr; DF; GC.

DB pt W.B. 1979t pt O.F; Tanks in way of tunnel 402t;

MT 1764t; FPT 114t; APT 242t.

7BH to U dk, 1 to 2nd dk; LACP

F 49' S

Rise of floor: Nil

"et" 2.3/8" SQ

INSERT IN S.R.L. APPENDIX

(Main structure partly
of P.403 Steel).

C.S.S. Records Dept.
to note.

P.403 Steel.
Dia. of chain cable
above Rule.

R.S.

12.11.58.

© 2020



Lloyd's Register
Foundation

003147 - 003153 - 0106