

ADDITIONS ABOVE LLOYDS RULES REQUIRED BY OWNERS

STRAKE 'A' INCREASED 0.5% - 25% FOR 1/2 L AMIDS.

"	"	"	"	"	"
"	"	"	"	"	"
"	"	"	"	"	"

STEENPOST 4% ABOVE RULE THICKNESS

RUDERSTOCK 15% " DIAMETER

INTERMEDIATE FRAMES AND INCREASED SHELLPLATING FORWARD (FOR ICE)

HEIGHT OF TANK SIDE BRACKETS, ABOVE BASE LINE INCREASED 145%

DOUBLE BOTTOM 3" DEEPER THAN REQUIRED BY RULES

HIGH TANK UNDER HOLD *3

BEAM KNEES FLANGED AS SHOWN ON PLAN

SHELTER DECK: 3 STRAKES OUTSIDE HATCHES INCREASED 10% 25% FOR 1/2 L AMIDS.

"	"	"	"	"	"
"	"	"	"	"	"
"	"	"	"	"	"

MAIN DECK: " " " " " " } HALF BEAMS INCREASED TO SAME SECTION
LOWER : : : : : 1.0 " } AS THROUGH BEAMS

HOLLOW PILLARS IN HOLDS AND LOWER TWEEDECK INCREASED IN THICKNESS

" " " " " " } UPPER TWEEDECK INCREASED IN DIAMETER AND THICKNESS

ANGLE BARS CONNECTING N°3 AND N°4 HATCHCOAMING TO SHELTERDECK MADE 130 x 130 x 12.5 (2x2 AG Riv.)

HATCHWAY BEAMS INCREASED

EQUIPMENT.

3 BOWE ANCHORS STOCKLESS A 3055 KO
1 STREAM --- INCL STOCK 1110
495 METER. 2 1/4" = 57 1/2" STUD CHAIN CABLE
165 " 4 1/4" = 121 " STEELWIRE
220 " 5" = 127 " ---
2 A 165 " 2 1/2" = 64 " ---
2 A 165 " 2" = 205 " MANILA

M.S. "AXEL JOHNSON".

GOTHENBURG REPORT N° 6177.

PLAN OF VESSEL AS BUILT.

DIMENSIONS

MIDSHIP-SECTION

003161-003174-0246 * 25020000