

Lloyd's Register of Shipping.

Ship's Name "BENEDICT".

Official No. 161147.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in

CLOSING OF TONNAGE OPENING.

The tonnage opening has now been permanently closed by fitting $\frac{3}{4}$ " thick steel plate supported by two fore and afters 6" x 3" B.A. welded to hatch coaming plate. The freeing ports in tonnage well have been permanently closed by welding plates in opening port and starboard sides and reinforced with strong back.

All overboard tween deck scuppers now removed, spigot patches riveted in way of ship's side and plate patches fitted on deck.

The shelter tween decks have now been fitted with scupper pipes draining to the bilges in machinery space, three 3" pipes Port and Starboard sides.

Suitable provision has been made for rigging lifelines by fitting eye bolts and steel wire ropes which are available for use of the crew to all parts of the ship for the regular working thereof.

Lockhart

SURVEYOR TO LLOYD'S REGISTER.

*Liverpool**Copy placed on board.*Forecastle bulkhead closing appliances.

*Two openings fitted with 3" shifting boards
in riveted channels.*

*Noted**24/7/42*

© 2020

Lloyd's Register
Foundation