

28 MAR 1946
28 MAR 1946

Lloyd's Register of Shipping.

Ship's Name "BENEDICT"

Official No. 161,147.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

Restoring of the Tonnage Opening.

(1). The Tonnage opening in the Shelter Deck now restored and fitted with efficient wood covers. ✓

The Tonnage openings in the Tonnage Well forward Bulkhead now closed by 3" boards fitted in Channels. ✓

(2). Scupper pipes on p.&.s. sides to drain the Shelter Tween Decks to Machinery Space bilges fitted with lever weighed cocks at their lower ends. ✓

Scupper pipes led to the Hold Bilges now permanently closed by E.W. plates.

Drain holes cut in the wings of Tween Deck Bulkheads to permit of the drainage of water to Scuppers led to Machinery Space bilges. ✓

(3). 5" diameter overboard scupper fitted on each side of the Tonnage Well with a screw down automatic non-return valve, controlled from the Shelter Deck, having an indicator showing when valve is open or closed. ✓

(4). All hatchways on the second deck have coamings, covers, supports, bearing surfaces, Tarpaulins, cleats, and battening arrangements in accordance with the Rules. ✓

() Renewal Load Line Survey carried out at this time. ✓

Markings verified and re-cut. ✓

New Load Line Certificate and copy issued. ✓

A. E. Macdonald

SURVEYOR TO LLOYD'S REGISTER OF SHIPPING.

LIVERPOOL.

27.3.46.

003191-003190-0083
W. Stead
J. B. D.
28/3/46



© 2020

Lloyd's Register Foundation