

"Succedbank"

Continuation of Report No.

dated

33836


on the

No 3. Hatchway on Foreboard Deck is now removed. Two oil. light hatches to new deep tank are fitted in lieu, each 9'-0" square with coaming $12 \times 3\frac{1}{2} \times 3\frac{1}{2} \times .46$ / .50 I. Steel. O. T. covers stiffened by bulb angles.

Two vents are fitted to deep tanks each. 6'-9" x 12" x 8/20 bracketed to deck & supported, with wooden plugs and canvas covers.

See ~~Box~~ Form C 11(c)

from Bel. dated 2/7/30



Lloyd's Register
Foundation

003181-003190-0300