

LLOYD'S REGISTER OF SHIPPING.

NOT IN R. B.

Copy

12 MAY 1928

PORT New Orleans, La.

April 26th, 1928

THIS IS TO CERTIFY that  
T.G.DODD

the undersigned Surveyor to this Society did at the request of  
v The Owner's Representative, Mr James McCall, survey the sternwheel  
paddle steamer "ZAPATOCA" 450 tons gross register of Barranquilla,  
Columbia, while laying afloat at the St Andrews Street Wharf,  
New Orleans, La. on April 25th, 1928, for the purpose of examining the  
towing arrangements made for a proposed voyage to Cartagina, Columbia,  
in tow of the Tug "SATOCO" of Port Arthur, Texas.

The towing arrangements consist of a one and one eighth stud  
link chain bridle, this bridle being led between the forward bitts and  
aft through the eyes of the forward cavil chocks in and out of the  
cavils with a turn round the aftermost chock and shackled round the  
after bitts on each side.

The tow line from the tug to the "ZAPATOCA" consists of two  
hundred fathoms of twelve inch manila hawser.

The hawser and bridle are in good condition and are properly  
thimble and secured.

A Navigation light has been securely fitted to the "ZAPATOCA".

Upon examination found the stern wheeler in good condition with all  
openings securely closed.

The stern wheeler has been boarded up and prepared for the voyage at  
Point Pleasant, West Virginia. for full particulars see report dated  
April 16th, 1928



© 2020

Lloyd's Register  
Foundation

003191-003199-0030 12



In my opinion the stern wheeler is now in proper condition for the proposed voyage, the towing arrangements and tug being approved.

FEE: \$ 55 <sup>00</sup>/<sub>100</sub>

*J. H. Wood.*

SURVEYOR TO,

LLOYD'S REGISTER OF SHIPPING.



© 2020

Lloyd's Register  
Foundation

0030 212