


LLOYD'S REGISTER OF SHIPPING.

PORT New Orleans, La.

April 26th, 1928

Copy



THIS IS TO CERTIFY that
T.G.DODD

the undersigned Surveyor to this Society did at the request of The Owners Representative, Mr James Mc Call, survey the Steel Stern-wheel paddle steamer "ZAPATOCA" 450 tons gross register of Barranquilla, Columbia, for the purpose of ascertaining the nature and extent of the damage alleged to have been sustained while on a voyage from Point Pleasant, West Virginia, to New Orleans, La. in tow.

On April 25th, 1928 while this vessel was laying afloat at the St Andrew Street Wharf, New Orleans, La. upon examination found the following damage and consequent repairs recommended:-

PORT FANTAIL:

Set in at about half length over a length of about six feet, top plate buckled, face channel set in and buckled and two angle stiffeners buckled. Face channel to be renewed, two angle stiffeners to be removed, faired and refitted and top plate to be faired in place, any started rivets to be renewed. On completion of repairs work to be coated.

The above recommendations have been made with a view to placing this vessel in the same condition as before the accident in question.

The above recommended repairs have not been carried out at this time, the damage not affecting the safe passage of the vessel to Cartagena Col. in tow.

It is estimated that the cost of repairs to the above damage would be \$ 250.00



© 2020

Lloyd's Register
Foundation

003191-003199-0031/2

FEES: - \$ 19 ⁰⁰/₁₀₀

J. H. Dodd

SURVEYOR TO,

LLOYD'S REGISTER OF SHIPPING.

Proprietor of Lloyd's Register of Shipping

BRISTOL 1258

2020



Lloyd's Register Foundation

Presented to the Lloyd's Register of Shipping

0031 2/2

Referred to the Chief Ship Surveyor.

[Handwritten signature]

12 MAY 1928

Also for Mr. Hill to note.

[Handwritten signature]

VOID, & INVALID ON SIGNING.

SEPARATION NO.

[Handwritten signature]



© 2020

Lloyd's Register
Foundation

10/00/01