

# Lloyd's Register of Shipping.

Ship's Name s.s. "CAPITOL"

Official No. 168182

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in

No. 1 hatch Macgregor's steel hatch covers renewed at this time with amended scantlings:-

5 covers, 2 webs in each  $10\frac{1}{2}"/5\frac{1}{2}" \times .32"$

spaced  $34\frac{1}{2}"$  to  $35\frac{1}{2}"$  apart

except forward covers  $37"$  and  $37\frac{1}{2}"$  apart

with face flats  $7\frac{1}{2}" \times 1"/7\frac{3}{4}" \times 1"$  forward cover

cross joint flats  $4" \times 1"$

centre line webs  $.32"$

top plating  $.34"$  except forward cover  $.37"$

side plating  $.38"$

side and end cleats  $39"$  apart

cross joint wedges  $48"$  apart.

*W. Robinson*

Surveyor to Lloyd's Register of Shipping,

West Hartlepool.

25-11-60.

*Noted & checked with plan  
approved 6/7/60  
20/12/60*

A copy of this report has been attached to the Load Line Report on board ship.

