

Dunston 31245
Rpt. 11b.

Index No. 31457
(For London Office only.)

Lloyd's Register of Shipping.

SURVEYS FOR FREEBOARD.—STEAM SHIPS.

PARTICULARS RELATING TO ALL STEAM SHIPS EITHER FLUSH DECKED, OR WITH TOP GALLANT FORECASTLES, SHORT POOPS AND BRIDGE HOUSES DISCONNECTED, OR WITH TOP GALLANT FORECASTLES HAVING LONG POOPS, OR RAISED QUARTER DECKS CONNECTED WITH BRIDGE HOUSES, OR OTHERWISE.

Port of Survey
Date of Survey June 1st 1932
Name of Surveyor

Ship's Name. **WILLIAM.**
Number in Register Book
Port of Registry and Nationality. **STOCKHOLM Swedish**
Official Number. **7,255**
Gross Tonnage. **2,016**
Date of Build. **1924/10.**
Particulars of Classification. **+100A1.**

Registered dimensions from Ship's Register.	LENGTH.	BREADTH.	DEPTH.	UNDER DECK TONNAGE.
	277.56	40.20	18.12	1647.45
Length on LOADLINE.	278.58	Frame Depth 8 $\frac{1}{2}$ Rule " 5 3 $\frac{1}{2}$ -58	Ceiling +20. Peak Sheer +52. 10 tanks top 18.5. General tank	33.79.
CORRECTED DIMENSIONS.	278.58	39.62	19.22.	1681.24

Co-efficient of fineness..... 79.
Any modification necessary { Para. 4 (a) to (e)* } .02 C.B.B.
Co-efficient as corrected 77.

Sheer { Stem..... 76 } 114 ÷ 2 = 57 ...Mean
at { Sternpost ... 38 }
Sheer at $\frac{1}{2}$ of the length from { Stem 41.75 } 62.50 ÷ 2 = 31.25 ...Mean
{ Sternpost 20.75 } ÷ 55 = 56.81
Gradual mean Sheer 56.81.
Standard mean Sheer [Table, Para. 18] 37.85. Correction
Difference..... 18.96 ÷ 4 = 4.76.
§ If limited as Para. 18 (f) -4 $\frac{3}{4}$.

Rise in Sheer { At front of bridge house.....
from amidships {
[Para. 18 (e)] { At after end of forecastle
Fall in Sheer {
Para. 18 (d) } ÷ 2 =
Length uncovered Correction

ALLOWANCE FOR DECK ERECTIONS:—

Freeboard, Table C..... 1 - 6.
Correction for Length, if required (Para. 12, 13, and 14) 1 $\frac{3}{4}$.
Freeboard by Table A, corrected for sheer, and for length, if required (Para. 11, 12, 13, and 14) } 3 - 11 $\frac{3}{4}$.
Difference 2 - 4
Percentage as below..... 24.62.
6.89

Correction for R. Q. Dk., if engine and boiler openings not covered by bridge house (Para. 11) }
Allowance for Deck Erections 7".
Length. Length allowed. Height.
Forecastle..... Sidehouse 6.75 25.50 7.5
Bridge House 58.50 62.75 7.0
† Raised Qr. Dk..... 7.0
Poop..... 21.62 21.62
Total 109.87 = 394
Length of Ship 278.58
Corresponding percentage { (Para. 11, 12, 13, and 14) } 24.62

Moulded Depth as measured..... 20-7 $\frac{1}{2}$.
Addition for Keel below base line for draught record..... inches.

NOTE.— If the depth is measured when vessel is afloat, the details of measurement should be reported.

CORRECTION FOR LENGTH.

Length of Ship on Loadline..... 278.58.
Length in Table 247.5
Difference 31.08
Correction for 10ft., Table A. 1.2 Table C. .6
× Difference divided by 10 3.729 (if required.) 1.86
If $\frac{1}{10}$ ths length covered divide by 2 +3 $\frac{3}{4}$. +1 $\frac{3}{4}$

CORRECTION FOR IRON DECK.

Proportion covered, if less than $\frac{1}{10}$ ths length covered 394.
Thickness of usual wood deck, less stringer 3 $\frac{1}{2}$ = 1.379.
-1 $\frac{1}{2}$

CORRECTION FOR ROUND OF BEAM.

Breadth at Gunwale amidships..... 40.0
Round of Beam 10"
Normal round..... 10"
Difference ÷ 2 =.....
Proportion of Deck uncovered (Para. 19)

NOTE.— The round of beam should be reported on the full breadth of vessel at the gunwale.

Freeboard, Table A 4 - 0 $\frac{3}{4}$.
Correction for Sheer 4 $\frac{3}{4}$.
3 - 8
Correction for Length 3 $\frac{3}{4}$.
3 - 11 $\frac{3}{4}$.
Allowance for Deck Erections 7
3 - 4 $\frac{2}{4}$
Correction for Round of Beam.....
Correction for fall in Sheer (if any).....
Correction for Steel Deck (if required) - 1 $\frac{1}{2}$.
3 - 3 $\frac{1}{4}$.
Additions for non-compliance with provisions of }
Para. 11 (d) and (e) † }
Other Corrections (if any)

Winter Freeboard 3 - 3 $\frac{1}{4}$.
Summer Freeboard 3 - 0 $\frac{1}{4}$.
Indian Summer Freeboard
N. A. Winter Freeboard

Correction necessary because clearside amidships, measured in accordance with the Statute is not taken at the intersection of the wood or steel deck with side.

Winter Freeboard from deck line
Summer " " " "
Indian Summer " " " "
N. A. Winter " " " "

SUMMER FREEBOARD amidships from Centre of Disc to top of Deck Line, Wood, Steel, Deck:—

Tropical Fresh Water Line above Centre of Disc ... 7.50 = 190.75 Tropical Fresh Water Freeboard ... 737 "
Fresh Water Line " " ... 4.50 = 114.75 Fresh Water " " ... 813 "
Tropical Line " " ... 3.0 = 76.5 Tropical " " ... 851 "
Winter Line below " " ... 3.0 = 76.5 Winter " " ... 1,003 "
Winter North Atlantic Line " " ... 5.0 = 127.5 Winter North Atlantic " " ... 1,054 "

15 JUN 1932

Use 1906-14-50.

MARKING FORM
21 JUN 1932
RECEIVED
- 2 FEB 1935
RECEIVED
13 JUN 1932

003200-003207-0113

© 2020

Lloyd's Register
Foundation