

2 AUG 1949

Rpt. C. 11 (Contd.)

Index No.

Lloyd's Register of Shipping.

Ship's Name m.s. "NUOLJA"

Official No. 7055

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines in 1932.

Accommodations amidship and aft completely renewed and deck houses amidship and aft partly renewed.

Entrance doors in deck houses fitted with steel hinged W.T. steel doors with 2 hinges and 4 toggles and sill 460 mm.

Escape hatches to holds and tween decks increased in size to 630 x 630 x 9 mm. 9 mm. steel hinged cover, 2 hinges, 2 toggles and rubber packing.

New open bulwark fitted from frame No.2 to frame No.48 and frame No.75 to forecastle (Fr.143) and also a closed bulwark on the forecastle.

Height of bulwark = 1070 mm.

The bulwark is efficiently supported by brackets at every 2nd frame, and fitted with expansion joints.

Length of bulwark = frame 2 to stem .7 x L = 86.408

Size of opening each side - 33.900 x 100

50.000 x 100 = 8.39 M²

Gothenburg, 27th July, 1949.

Handwritten signature

Handwritten note: "checked"

3 AUG 1949



© 2020

Lloyd's Register
Foundation

003223-003232-0032