

1m, 9, 20.

FREEBOARD REPORT on the


Jotavertken NO 361 & 362.

3½

This submitted Mr Mellin be informed that if the vessels are built with open shelter decks, the moulded draught corresponding to a moulded depth to upper deck of 30'-0" would be about 25'-11½". This draught is determined on the assumption that bulkheads are fitted between the upper and shelter decks forward and aft of the tonnage opening and that the freeboard coefficient is .77.

Defer for
mld. depth
For Mr Lums.

not sent
moulded depth
W.D.S.
25.11.22
29.11.22
W.D.S.



© 2020

Lloyd's Register
Foundation

003223-003232-0034

could be reduced point draught 1 inch.

4-6½