

C O P Y

O R D E R

Tel: Add: "Belliss, B'ham"
Telephone: Edgbaston 2001
(6 lines)

No. 7720.

B E L L I S S & M O R C O M L I M I T E D

All communications
to be addressed to
the Company at
Ledsam Street Works

E N G I N E E R S,

LEDSAM STREET WORKS,

Birmingham. 16, Sept. 16th - 1938.

To: The British Thomson-Houston Co. Ltd.,
R U G B Y.

FOR TERMS & CONDITIONS UPON WHICH THIS ORDER IS PLACED SEE BELOW AND OVER

PLEASE APPLY FOR FORWARDING INSTRUCTIONS WHEN GOODS ARE READY

SERVICE:- **GREENOCK DOCKYARD CO. LTD. NOS. 9562/3/4 DYNAMO ENGINES FOR**
CLAN LINE STEAMER NO. 437.

Please deliver Carr: Paid to

Your Electrical Machinery Department, Icknield
Square Works, Birmingham, suitably packed for re-delivery to destination
by rail transit. Lids of cases to be left unsealed.
Despatch must not be effected without our written instructions.

THREE - 125 K.W., 220 Volts, 500 rpm. compound wound, marine type D.C.
GENERATORS, with drip proof enclosures, and to be suitable for
running in parallel. Each machine to be provided with
single pedestal bearings, rigid half coupling (to our dimen-
sions) sheet metal liners and set pins, and arranged for
mounting upon the extension of our engine baseplate.

Also three radial back-of-board type shunt field REGULATORS, including
chromium plated handwheels and dialplates.

OVERLOAD CAPACITY:- In accordance with B.S.S. 168-1926.

TEMPERATURE RISE:- Not to exceed 63 degs.F. above that of the sur-
rounding atmosphere after six hours continuous run at full load.

EFFICIENCIES:- Please state figures at full, 3/4, and 1/2 loads.

SPARE GEAR:- One set only, comprising the following items :-

- 2 sets brushes.
- 2 lines brush holders and spindles.
- 1 bearing liner.

(To be suitably packed for storage aboard ship).

Continued.....

Time or as may
be required under the penalty specified for our gross contract as and for
liquidated damages

This o/r confirms letter

instructing you to put the work
in hand
For BELLISS & MORCOM LIMITED

Exd.

Director

Nearest Goods Stations: L.M.S.Rly. Central Station, Suffolk Street, B'ham
G.W.R.Rly. Hockley Station, Birmingham

C O P Y

O R D E R

Tel: Add: "Belliss, B'ham"
Telephone: Edgbaston 2001
(6 lines)

No. 7721.

B E L L I S S & M O R C O M L I M I T E D
E N G I N E E R S,

LEDSAM STREET WORKS,

Birmingham. 16, Sept. 16th - 1938.

All communications
to be addressed to
the Company at
Ledsam Street Works

To: The British Thomson-Houston Co. Ltd.,

R U G B Y.

FOR TERMS & CONDITIONS UPON WHICH THIS ORDER IS PLACED SEE BELOW AND OVER

PLEASE APPLY FOR FORWARDING INSTRUCTIONS WHEN GOODS ARE READY

SERVICE:- GREENOCK DOCKYARD CO. LTD. - Ship No. 437.

~~Please deliver Carriage Paid to~~

TERMS OF PAYMENT:- Nett Cash as per Conditions of Sale "A".
Payment being made as and when received by us.

The above equipment to be complete with all fittings and accessories, and in accordance with our Enquiry No. 107 dated May 17th, your quotation ref. MEC/Q.685267 of May 20th, letters dated July 26th and 28th, our customers requirements, and other correspondence.

TESTS & TEST CERTIFICATES:-

Full load tests to demonstrate the temperature rise and efficiencies of the machines are to be taken at your Works, and certificates submitted to us in triplicate.

The above sets are to conform to Lloyds and Board of Trade requirements.

INSPECTION:- Concerning inspection fees, our customers give the following instruction which we are requested to pass on to you.

"With regard to the fee quoted to you by the B.T.H. Co. Ltd."
"we have been in communication with Lloyds who have informed"
"us that that firm should instruct Lloyds Surveyor to call"
"as required for tests and construction; that such fees are"
"covered for in the payment we make for electrical installation"
"and that the only charge that Lloyds will make for visiting"
"British Thomson-Houston Co's Works will be the expenses"
"incurred in connection with travelling etc. and this will be"
"charged directly to the Greenock Dockyard Co. Ltd."

PAINTING:- Dull black, as usual.

B.E.A.M.A. Conditions of Sale "A" govern this order.

Time APPROX. Middle of AUGUST 1939 or as may
be required under the penalty specified for our gross contract as and for
liquidated damages

This o/r confirms letter 7th instant, instructing you to put the work
in hand
For BELLISS & MORCOM LIMITED

Exd.

(Sgd) John Belliss
Director

Nearest Goods Stations: L.M.S.Rly. Central Station, Suffolk Street, B'ham
G.W.R.Rly. Hockley Station, Birmingham

Bridge Deck, Angle, E or L