

TRANSLATION.

TRANSLATION.

M.S. "TABIAN".

Continuous Survey.

I the undersigned Surveyor, appointed by the Lloyd's Agent, hereby certify that I have carried out a survey of the starboard sea water main cooling pump and of the lower donkey boiler.

1 Starboard sea water main cooling pump.

This pump has been examined dismantled. It is of the two stage centrifugal type. The shaft is in good condition, as well as the impellers and the two stator halves. The clearance between the drums and the housings has been checked, and the clearance between the casing halves adjusted to 0.2 milli.

The stuffing boxes have been repacked.

I am of the opinion that this pump is in an efficient condition to be recommissioned for a further period of four years.

2 Lower donkey boiler.

The boiler has been completely examined internally and externally; it shows no signs of wear or corrosion. Moreover, this boiler obviously has been little used. All the boiler mountings have been inspected and found in excellent condition after a light grinding-in of the valves. The safety valves have been dismantled and checked.

The furnaces have been examined and found in good condition and the burners and accessories appear in good condition.


I did not deem it necessary to carry out a hydraulic test of the boiler, which is kept empty and dry. It was not considered necessary to fill and light the boiler for the purpose of setting the safety valves, which will have to be adjusted when the boiler is put into service.

A provisional certificate has been issued (for wording of this see original report).

DAKAR the 5th January, 1962.

(signed) P. Degorce.

Surveyor appointed by Lloyd's Agent.



© 2020

Lloyd's Register  
Foundation

003290-003297-0171