


## LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

CPN. 1ST ENTRY REPORT NO. 14646Port Copenhagen23<sup>rd</sup> March, 1954.

## This is to Certify that

G. Severin

the undersigned Surveyor to this Society did at the request of  
Messrs. Møller & Jockumsen A/S of Horsens on the 12<sup>th</sup> March 1954 and  
on subsequent date attend their works for the purpose of examining and  
testing

one completely overhauled two-stroke-cycle  
single acting heavy oil engine designated no. 1037.

The particulars of the engine are as follows:

H.P.	90
Number of cylinders	2
Bore	180 mm
Stroke	300 mm
P.M.	500 mm

The cooling water passages of the cylinders, covers, silencer and  
oil cooler were in my presence subjected to hydraulic pressures as  
stated below and found good and tight. Brinell tests taken on the  
crank shaft correspond to a tensile strength of 54 kg/sq.mm. All  
parts examined and found in good working order.  
The engine was tested under full power working conditions in shop  
and found satisfactory.

Tests for identification:-

Cylinders & covers	Test	7 atm.	G.S. 12.3.54
Silencer	Test	3,5	G.S. 12.3.54
Lubricating oil cooler	Test	5	G.S. 12.3.54
Crank shaft			G.S. 12.3.53

The engine has not been built under special survey.  
It is stated that the engine is intended for m.t. "Esso København"  
Copenhagen.

& Exp: Kr. 310.00

*G. Severin*  
SURVEYOR TO LLOYD'S  
REGISTER OF SHIPPING

This certificate is issued upon the terms of the Rules and Regulations of the Society, which provide that:—

The Committees of the Society use their best endeavours to ensure that the functions of the Society are properly  
carried out and to be understood that neither the Society nor any Member of any of its Committees is under any circumstances  
to be held responsible for any inaccuracy in any report or certificate issued by the Society or its Surveyors, or in any  
Register Book or other publication of the Society, or for any error of judgment, default or negligence of any of  
its Surveyors or any Member thereof, or the Surveyors, or other Officers or Agents of the Society."