

Lloyd's Register of Shipping.

Ship's Name PETER HURLLOfficial No. ---

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines
in MAY, 1931.

The following companions additional to those reported in the
original Rpt.C11 have been found fitted:

In side house under forecastle deck on port side to pumproom and
on starboard side to forward dry cargo hold; openings 1475/600, sill
360mm. From after bridge deck two steel companions to forward
accommodation and two steel companions to after accommodation.
Openings 1475/600, height of sill 380mm above wood deck.

All above openings fitted with strongly constructed hinged steel
doors with turnbuckles, capable of being manipulated from both sides.

The steel hinged door in bridge after bulkhead found removed and
the opening permanently closed by a riveted plate.

(Ham., Feb., 1939).

Noted
100
1/3/39

