

LLOYD'S REGISTER OF SHIPPING

UNITED WITH THE BRITISH CORPORATION REGISTER

ALTERATIONS TO CONDITIONS OF ASSIGNMENT OF LOADLINES

Ship's Name "BRITAMER" Official No. ✓


Port of Registry DUBLIN

This ship has been under survey at Wallsend-on-Tyne
on 20th October (and subsequently) 1954 and the following alterations to the conditions of assignment of loadlines have now been effected/~~found~~:-

BRIDGE FRONT An opening 4'6" x 2'6" has been cut in Bridge front and a strongly constructed hinged ^{steel} door has been fitted and secured by 6 clips, operable both sides, with 24" high coaming above deck.

Bridge front suitably compensated for opening.

POOP FRONT Steel plates, with hook bolts spaced about 12" apart have been fitted to existing tonnage openings (p.s.), in addition to previously fitted weather boards



G. Buchanan

J.S.G.

23 NOV 1954

A copy of this Report has ^{NOT} been placed on board.

