



SWITCHBOARD CONNECTIONS WITH SINGLE DYNAMO CIRCUIT

& OUTGOING CIRCUITS CONTROLLED BY DOUBLE POLE SWITCHES.

DYNAMO.

D.P. QUICK BREAK MAIN SWITCH 35 AMPS.

TWO S.P. PORCELAIN HANDLE FUSES 35 AMPS.

OUT GOING CIRCUITS 3 OFF

D.P. QUICK BREAK SWITCH 35 AMPS.

TWO S.P. PORCELAIN HANDLE FUSES 15 AMPS.

INSULATION OF LIVE PARTS.

SINDANYO PANEL SELF INSULATING

— OR —

SLATE OR MARBLE PANEL INSULATED WITH

MICANITE TUBES & WASHERS

ALL LIVE TERMINALS

FITTED WITH LOCK NUTS.

To be insulated from frame in which it is mounted in same way.

SK. No 34/20

Telford, Grier, Mackay & Co., Ltd.,

GLASGOW

© 2020

Lloyd's Register Foundation

003321-003327-0206

AUSA SB. Co's 421/2.

421 "The President"

422 "The Earl."

Elect. Equipment

~~GEN BOX NO~~

~~140 A~~

~~London copy~~

(4)



© 2020

Lloyd's Register
Foundation

003321-003327-0206