

Alterations in C 11 report S.S. "SAECA"

Aftermost skylight on poop deck removed.

Store hatch fitted in way 39" x 39", height above deck 28",
2 3/4" wooden F & A fitted covers, 5" bearing, cleats, battens &
tap anails fitted.

7 screw down muck room vents on poop deck fitted

2 hinged steel doors, fitted in poop front bulkhead leading
to lavatories, which have no communication inside
with crew's accommodation and all surrounded by
efficiently constructed steel bulkheads.

6 hinged steel doors in forecastle bulkhead permanently
closed by riveted plates.

1 opening made in middle of bulkhead 6' x 4', sill 12"
closed by storm boards in riveted channels.

August 1939

H. J. G. Hoff

Noted *BZ*
11.9.39.