

## Lloyd's Register of Shipping.

F. 947 Svg.

Ship's Name

M. V. "HEATHER"

Official No.

Memorandum of alterations reported since ship was surveyed for assignment of Load Lines  
~~in~~ since building.

The hatch coamings on the main deck, 4 each at port and starboard sides, to the wing cargo holds now removed and the deck openings permanently closed with riveted steel plates.

Ventilator coaming to the pump room on the trunk deck now removed and the deck opening permanently closed with riveted steel plate.

Ventilators fitted on the main deck to the Nos.1,2,3 and 4 port and starboard wing cargo holds and on the trunk deck to the Nos.1,2,3 and 4 centre cargo holds.

## DESCRIPTION OF VENTILATOR COAMINGS ON THE MAIN DECK:-

Coaming thickness 0.35 inches, diameter 12 inches, height 93 inches.

## VENTILATOR COAMINGS ON THE TRUNK DECK:-

Coaming thickness 0.40 inches, diameter 18 inches, height 36 inches.

All ventilator coamings suitably supported and secured and, provided with wood plugs and canvas covers.

W. P. Watson



LQ

4 FEB 1953

