

Ship's name "BALLYKNOCK"

Port BEL

Class is subject to

Nil

Last survey

ES due 10.62 now commenced.

Docking screwshaft examined.

MBS due 8.62 now held.

General examination of machinery now carried out in accordance with circular 1959 and all found satisfactory.


Screwshaft continuous liner found worn in way of stern gland packing and whilst the liner is considered to remain efficient meantime the surveyor recommends that the screwshaft liner be specially examined at the next annual dry docking due September 1963 and the screwshaft record being withheld meantime.

IT IS SUBMITTED that this vessel is eligible to remain as classed with fresh record of MBS 8.62 now and TS CL (with date) subject to screwshaft liner being examined and dealt with as necessary at the next annual dry docking (due September 1963) and ES (with date) when the survey is completed, screwshaft survey record to be withheld meantime.


28.9.62

Submitted the proposal for postponement of special survey merits the favourable consideration of the committee.

To complete ES all Rule Requirements to be complied with except HP, MP and LP cylinders, pistons, rods and valve gear, main engine driven pumps, main circulating pump and engine, GS pump and Ballast pump, steering and windlass and dynamo engine.



Lloyd's Register
Foundation

