

G.R. 130.

(LLOYD'S REGISTER.)
VESSELS OF 100 TONS AND UPWARDS.

These particulars are supplied by the Registrar General of Shipping and Seamen for the sole use of Lloyd's Register of Shipping.
Signal Letters (if any) G.Z.C.G.

Signal Letters (if any)		Official Number.	Name of Ship.	No., Date, and Port of Registry.		
		165154	GLENGARRIFF	10 in 1936 Belfast.		
No., Date, and Port of Previous Registry (if any).			New Vessel			
Whether British or Foreign Built.		Whether a Sailing, Steam, or Motor Ship, if Steam or Motor Ship how propelled.	Where Built.	When Built.	Name and Address of Builders.	
British		Steam Screw	Aberdeen	1936	J. Lewis & Sons Ltd. Albert Quay Aberdeen	
Number of Decks One			Length from fore part of stem, under the bowsprit, to the		Feet.	Tenths.
Number of Masts three			aft side of the head of the stern post		197	7
Rigged Schooner			Length at quarter of depth from top of weather deck at side		197	0
Stern Cruiser			amidships to bottom of keel			
Build Clencher			Main breadth to outside of plank plating		30	7
Galleries None			Depth in hold from tonnage deck to ceiling at midships		12	1.5
Head None			Depth in hold from upper deck to ceiling at midships, in the		-	-
Framework and description of Steel Cargo			case of three decks and upwards		14	9.2
vessel			Depth from top of beam amidships to top of keel		14	3.7
Number of Bulkheads three			Depth from top of deck at side amidships to bottom of keel ..			6.7
Number of water ballast tanks, Five			Round of beam			2.5
and their capacity in tons .. 299 tons			Length of engine room, if any		43	

PARTICULARS OF DISPLACEMENT.

Total to quarter the depth from weather deck at side amidships to bottom of keel	1371	Tons.	Ditto per inch immersion at same depth	11.74	Tons.
---	------	-------	---	-------	-------

PARTICULARS OF PROPELLING ENGINES, &c. (if any).

No. of sets of Engines.	Description of Engines.	Whether British or Foreign Made.	When made.	Name and address of makers.	Reciprocating Engines.		Rotary Engines.	N. H. P. E. H. P. I. H. P. Speed of Ship.
					No. of Cylinders in each set.	Length of Stroke.		
One	Reciprocating Steam triple direct acting vertical	Engines. British	Engines. 1936	Engines. J. Lewis & Sons Ltd. Aberdeen	3 14 1/2" 25"	30"	-	102.7 660 775
No. of Shafts.	Particulars of Boilers. Description _____ Multitubular Number _____ One Iron or Steel _____ Steel Loaded Pressure _____ 200 lbs per sq. inch	Boilers. British	Boilers. 1936	Boilers. J. Lewis & Sons Ltd Aberdeen	41"			10 knots
One								

PARTICULARS OF TONNAGE.

GROSS TONNAGE.	No. of Tons.	DEDUCTIONS ALLOWED.	No. of Tons.
Under Tonnage Deck	<u>597.50</u>	On account of space required for propelling power	311.29
Space or spaces between Decks.. .. .		On account of spaces occupied by Seamen or Apprentices, and appropriated to their use, and kept free from goods or stores of every kind, not being the personal property of the Crew	49.64
Turret or Trunk	24.00		
Forecastle	19.90	These spaces are the following, viz. :—	
Bridge space	<u>126.44</u>	Forecastle Bridge and Round House	
Poop or Break	14.15	(Number of Seamen or Apprentices for whom accommodation is certified....13.....).	
Side Houses.. .. .	5.01		
Deck Houses		Deductions under Section 79 of the Merchant Shipping Act, 1894, and Section 54 of the Merchant Shipping Act, 1906, as follows :—	
Chart House	30.22	Master's Accn 5.52	
Spaces for machinery, and light, and air, under Section 78 (2) of the Merchant Shipping Act, 1894	51.23	Chart Space 5.01	51.46
Excess of Hatchways		Bosn's Store 10.00	
		W.B. Spaces 30.93	
Gross Tonnage	<u>868.45</u>	Cubic Metres.	
Deductions, as per Contra.. .. .	<u>412.39</u>		
Register Tonnage	<u>456.06</u>		
		Total	412.39

NOTE 1.—The tonnage of the engine room spaces below the Upper Deck is 147.66 tons, and the tonnage of the total spaces framed in above the Upper Deck for propelling machinery and for light and air is 34.76 tons.

Open Space Aft Forecastle = 11.69 tons

Name of Master

Certificate of

{	Service	No.
	Competency	No.

No. of Owners

Name, Residence, and Description of Managing Owner: if there are more owners than one.

John Kelly Limited having its principal place of business at
Station Street in the County of the City of Belfast.

Sixty-four (64) shares.

Dated 29 August, 1936.

