

C O P Y .

126'-0" Wooden Minesweeper.

Having examined the midship section B.A.T.M. Dwg.No. 6/102, date 23/10/42, it appears that, based on Table A, the period of years are as follows:-

Floors and 1st Futtock Y Birch 7 years

Table A does not give birch for 2nd futtocks.

3rd futtocks and top timbers Spruce 8 years

Keelson O Pine 9 years

Beams Spruce 8 years

Beam knees spruce 8 years

Bottom planking Y.Birch 10 years

Topside planking spruce 8 years

Mixed material 7
1
roof 1

9 years

Yellow birch (Betula Lutea) is the standard name. Black birch is one of the many names given to yellow birch.

Two coats of Cuprinol, generously applied, are, in my opinion, equal to salting, and the above table assumes this provision.

(sgd) G.S.

14.9.44

It is submitted the Reports Department and Mr.Bennett be informed accordingly.

(sgd) E.P.



Lloyd's Register Foundation

003434-003443-0208